

PART VI: 15-MONTH EXECUTION MILESTONE SCHEDULE

Contract Time Schedules, Work Progress Stages & Financial Penalties

Execution Milestone Timeline (Total 15 Months Duration):

- Milestone 1 (Month 2): Submission of Geotechnical Investigation & Vetted Structural Drawings (10%)
- Milestone 2 (Month 5): Substructure completion & plinth beam casting across all 7 stations (25%)
- Milestone 3 (Month 8): Superstructure RCC frame completion & FLN additional floor slab casting (55%)
- Milestone 4 (Month 11): Brickwork infill, internal/external plastering, and door/window frames (75%)
- Milestone 5 (Month 14): Flooring, internal electrical wiring, plumbing, sanitary fixtures & painting (95%)
- Milestone 6 (Month 15): Testing, commissioning of services, site cleanup, and final handover (100%)

Liquidated Damages: Imposed per GCC Clause for failure to achieve critical scheduled milestones