

FLN SERVICE BUILDING VERTICAL EXTENSION CHARTER

Additional Floor Construction over Existing Operational DFC Service Building

Specialized Work Component at Phulera (FLN) DFCCIL Station:

- Structural Stability Assessment: Non-destructive testing (NDT) of existing ground floor frame
- Column Jacket Retrofitting: Micro-concreting and epoxy anchoring into existing roof slab columns
- Superstructure Expansion: Additional upper floor accommodating operational offices and rest suites
- Roof Weatherproofing: High-performance elastomeric waterproofing and terracotta tile terracing
- Live Railway Station Interface: Construction execution without interrupting round-the-clock DFC freight traffic