



इंजीनियरिंग प्रोजेक्ट्स (इंडिया) लि.

(भारत सरकार का उद्यम)

ENGINEERING PROJECTS (INDIA) LTD.

(A Government of India Enterprise)

TENDER DOCUMENT

NIT No.: EPI/CO/CON/977/861

Dated: 25.09.2024

FOR

Tender for “Construction of E-Type Staff quarters (S+4) including Architectural Consultancy services For ICDS Staff Quarters at Kendrapara, Odisha”.

VOLUME – III

Price Bid/BOQ

ENGINEERING PROJECTS (INDIA) LIMITED

(A GOVT. OF INDIA ENTERPRISE)

Core-3, Scope Complex,

7, Lodhi Road, New Delhi-110003

TEL NO: 011-24361666, FAX NO. 011- 24363426

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Engineering Projects (India) Ltd., New Delhi

Name of Work: Tender for Construction of E-Type Staff Quater (S+4) For ICDS Staff Quater at Dhenkanal, Odisha. (2nd Call)

Contract No: EPI/CO/CON/977/861

Name of the Bidder/ Bidding Firm / Company :							
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT EXCLUDING GST in Rs. P	TOTAL AMOUNT INCLUDING GST in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Construction of E-Type Staff Quater (S+4) For ICDS Staff Quater at Dhenkanal, Odisha (2nd Call) including Architectural Consultancy services.	1.000	LS	71033175.00	71033175.00		INR Seven Crore Ten Lakh Thirty Three Thousand One Hundred & Seventy Five Only
Total in Figures					71033175.00		INR Seven Crore Ten Lakh Thirty Three Thousand One Hundred & Seventy Five Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Name of Work-Tender for Construction of E-Type Staff Quater (S+4) For ICDS Staff Quater at Dhenkanal, Odisha. (2nd Call)		
NIT No- PCO/BBSR/977/196 Date-12.09.2024		
SUMMARY		
SL. NO.	DESCRIPTION	AMOUNT IN Rs.
A	Architectural Consultancy services.	7,03,298.76
	Total (A)	7,03,298.76
B	EXECUTION	
1	Civil Works	4,65,93,376.88
3	P.H Works	54,69,462.34
4	Internal Electrical Works	55,95,963.00
5	Lightening Arrester	5,68,374.00
6	Substation	37,60,000.00
7	EXTERNAL ILLUMINATION	11,45,493.00
8	LIFT (8 Passenger)	14,50,000.00
9	Boundary Wall, Guard Room & Road	50,05,907.36
10	FIRE FIGHTING WORK	7,41,299.87
	TOTAL (B)	7,03,29,876.45
	GRAND TOTAL (A+B)	7,10,33,175.00

Name of Work-Tender for Construction of E-Type Staff Quater (S+4) For ICDS Staff Quater at Dhenkanal, Odisha. (2nd Call)					
NIT No- PCO/BBSR/977/196 Date-12.09.2024					
Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	CIVIL WORKS (Super structure)				
1	Earth work in all kind of soil within 50m, initial lead and 1.5m, initial lift including rough dressing not exceeding 0.3m in depth and the earth transported by transport vehicles as directed by the Engineer-in-charge.	Cum.	232.30	795.74	1,84,850.40
					-
2	Excavation of foundation trenches and column foundation and pits of extra lift over the initial lift of 1.5 mtrs. but upto 7.50 mtr. Depth in all kind of soil as per direction of the Engineer-in-charge.	Cum.	249.10	530.49	1,32,145.06
					-
3	Filling foundation trenches and plinths with excavated materials in layers not exceeding 0.3 mtr in depth including watering and ramming and dressing and levelling etc. complete as per the direction of the Engineer-in-charge.	Cum.	156.40	463.26	72,453.86
					-
4	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 1 K.M initial lead, for all leads including all lifts involved.	Cum.	378.00	795.74	3,00,789.72
					-
5	Filling in foundation trenches and plinths with filling sand, well watered, compacted, dressed and leveled to proper gradient etc., complete as per the direction of the Engineer-in-charge.	Cum.	555.70	357.15	1,98,468.26
					-
					-
6	ANTI-TERMITE TREATMENT :				-
					-
	Supplying , diluting and and preparing chemical emulsion like CHLORPYRIPHOS or other chemicals approved by central Insecticides Board or as directed by the manufacturer and spraying the mixture uniformly by sprayer as pre-constructional anti termite treatment and creating a chemical barrier under and around wall trenches, basement excavation, top surface of plinth filling, junction of walls and floors along with external perimeter of the building, surrounding the pipes and conduits etc. complete at the rate of 7.5 litres (or as directed by the manufacturer) per sqm on vertical and 5.0 liters per sqm on horizontal surfaces, 50% of the emulsion to be filled in the holes made in trenches at 150mm center to center etc. complete.as per IS:6313/1981 (PART-II) and as per the direction of engineer-in-charge including all cost of materials labour, taxes etc. all complete.	Sqm.	142.00	364.00	51,688.00
					-
7	Providing and laying of P.C.C. of 1:4:8 with 4 c.m size hard granite metal in foundation trenches, under floors in line level including curing and ramming etc. all complete as per the direction of the Engineer-in-charge..	Cum.	5,197.00	122.21	6,35,125.37
					-
					-
4	R.C.C. work of M-25 grade with 20mm and down grade black hard granite (crusher broken) stone chips including hosting and laying etc. all complete as per the direction of the Engineer-in-charge.				-
					-
	Foundation	Cum.	6,679.00	289.60	19,34,238.40
					-
	Plinth beam	Cum.	6,679.00	94.00	6,27,826.00
					-
	Stilt floor	Cum.	6,679.00	120.90	8,07,491.10
					-
	First floor	Cum.	6,771.50	130.60	8,84,357.90
					-
	Second floor	Cum.	6,877.80	130.60	8,98,240.68
					-
	Third floor	Cum.	7,000.10	130.60	9,14,213.06
					-
	Fourth Floor	Cum.	7,140.70	130.70	9,33,289.49
					-
	Terrace floor	Cum.	7,302.40	15.68	1,14,501.63
					-
5	Providing smooth centering & shuttering for R.C.C works including false works and dismantling then after casting including cost of materials complete as per the direction of the Engineer-in-charge.				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
					-
	Foundations, footings, bases of columns etc. for mass concrete.	Sqm.	236.40	518.40	1,22,549.76
					-
	Suspended floors, roofs, landings, balconies and access platform.	Sqm.	1,017.12	1,781.65	18,12,151.85
					-
	Columns, beams, plinth beams, girders, bressumers and cantilevers, staircase	Sqm.	1,529.34	4,339.57	66,36,677.98
					-
					-
	Lintels	Sqm.	691.86	556.31	3,84,888.64
					-
6	Providing M.S reinforcement for R.C.C work including cutting, bending, and tying the grills and placing in position including cost of binding wire 18 to 22 gauge etc. complete as per the direction of the Engineer-in-charge.				-
					-
					-
	Foundation	Qntl.	8,919.00	268.80	23,97,427.20
					-
	Stilt floor	Qntl.	8,919.00	343.94	30,67,600.86
					-
	First floor	Qntl.	8,945.00	209.08	18,70,220.60
					-
	Second floor	Qntl.	8,972.00	196.01	17,58,601.72
					-
	Third floor	Qntl.	9,000.00	196.01	17,64,090.00
					-
	Fourth floor	Qntl.	9,030.00	196.18	17,71,505.40
					-
	Fifth Floor	Qntl.	9,061.00	23.52	2,13,114.72
					-
					-
7	Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$ in cement mortar (1:6) in 230 mm thick wall, immersing the bricks for minimum 6 hrs in water before use, in foundation & plinth as per the direction of the Engineer-in-charge .	Cum.	5,123.00	31.30	1,60,349.90
					-
8	Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$ in cement mortar (1:6) in 230 mm thick wall, immersing the bricks for minimum 6 hrs in water before use, in Super structure as per the direction of the Engineer-in-charge .				-
					-
	Stilt floor	Cum.	5,156.00	24.79	1,27,817.24
					-
	First floor	Cum.	5,446.00	119.85	6,52,703.10
					-
	Second floor	Cum.	5,779.60	119.85	6,92,685.06
					-
	Third floor	Cum.	6,163.30	119.85	7,38,671.51
					-
	Fourth floor	Cum.	6,604.50	119.85	7,91,549.33
					-
	Fifth floor	Cum.	7,111.90	49.94	3,55,168.29
					-
					-
9	Reinforced Brick work with Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$ in cement mortar (1:4) in 230 mm thick wall, immersing the bricks for minimum 6 hrs in water before use, in Super structure as per the direction of the Engineer-in-charge .				-
					-
	Stilt floor	Cum.	5,466.00	10.00	54,660.00
					-
	First floor	Cum.	5,748.00	30.04	1,72,669.92
					-
	Second floor	Cum.	6,085.00	30.04	1,82,793.40
					-
	Third floor	Cum.	6,473.00	30.04	1,94,448.92
					-
	Fourth floor	Cum.	6,918.00	30.04	2,07,816.72

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
					-
10	Providing average 25 mm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips as per the direction of the Engineer-in-charge.	Sqm.	554.20	323.81	1,79,455.50
					-
					-
11	Providing Avg. 12 mm thick cement plaster 1:6 (1 cement : 6 sand) to inside surface etc. as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	157.20	62.89	9,886.31
					-
	First floor	Sqm.	160.80	733.01	1,17,868.01
					-
	Second floor	Sqm.	164.50	733.01	1,20,580.15
					-
	Third floor	Sqm.	168.30	733.01	1,23,365.58
					-
	Fourth floor	Sqm.	172.20	733.01	1,26,224.32
					-
	Fifth floor	Sqm.	176.20	75.16	13,243.19
					-
					-
12	Providing Avg. 16 mm thick cement plaster 1:6 (1 cement : 6 sand) to outside surface etc. as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	223.80	543.18	1,21,563.68
					-
	First floor	Sqm.	229.20	450.24	1,03,195.01
					-
	Second floor	Sqm.	234.70	450.24	1,05,671.33
					-
	Third floor	Sqm.	240.40	450.24	1,08,237.70
					-
	Fourth floor	Sqm.	246.30	450.24	1,10,894.11
					-
	Fifth floor	Sqm.	252.30	412.43	1,04,056.09
					-
13	Providing average 6 mm thick cement plaster(1:4) to R.C.C surfaces finished smooth including deep chipping & slurring treatment etc. complete.as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	174.80	336.99	58,905.85
					-
	First floor	Sqm.	179.00	299.76	53,657.04
					-
	Second floor	Sqm.	183.30	299.76	54,946.01
					-
	Third floor	Sqm.	187.80	299.76	56,294.93
					-
	Fourth floor	Sqm.	192.40	299.76	57,673.82
					-
	Fifth floor	Sqm.	197.10	21.49	4,235.68
					-
14	Providing & applying cement punning over cement plaster.	Sqm.	35.80	200.00	7,160.00
					-
15	Providing plaster drip course/ groove in plastered surface or moulding to R.C.C.projections. of size 40 mm x 12 mm deep in cement mortar proportion 1 : 3.	Mtr.	34.00	200.00	6,800.00
					-
16	Supplying 150 mm wide Chicken wire mesh of standard quantity as availble in local market & fixing with U nails 150 mm center to center before plastering the junction of walls and beam/column in one vertical plane to prevent surface cracks appearing between junctions of column / beam and walls before plastering. Payment shall be made by measuring the chicken wire mesh.	Sqm.	141.00	250.00	35,250.00
					-
17	Providing and applying 2 coats with 100% acrylic emulsion paint (exterior quality) of approved make & shade by reputed manufacturer to make an even finished surface over a coat of primer with water bound cement primer in all heights with all scaffolding and staging charges including cost , conveyance, taxes of all materials, cost of all labours , T & P, sundries etc. as required for the work complete.				-
					-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Stilt floor	Sqm.	137.10	543.18	74,469.98
					-
	First floor	Sqm.	140.40	450.24	63,213.70
					-
	Second floor	Sqm.	143.80	450.24	64,744.51
					-
	Third floor	Sqm.	147.30	450.24	66,320.35
					-
	Fourth floor	Sqm.	150.90	450.24	67,941.22
					-
	Fifth Floor	Sqm.	154.60	412.43	63,761.68
					-
18	Supplying and painting of internal walls and ceiling with two or more coats of acrylic emulsion paint which includes two coat of internal putty with a coat of primer all complete. The shade and brand to be of approved brand & shade over the surfaces including preparation of surface, with cost of all materials, labour, conveyance taxes of all materials,scaffolding etc., as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	245.50	399.87	98,168.09
					-
	First floor	Sqm.	250.30	1,032.77	2,58,502.33
					-
	Second floor	Sqm.	255.20	1,032.77	2,63,562.90
					-
	Third floor	Sqm.	260.20	1,032.77	2,68,726.75
					-
	Fourth floor	Sqm.	265.40	1,032.77	2,74,097.16
					-
	Fifth Floor	Sqm.	270.70	96.65	26,163.16
					-
					-
19	Synthetic enamel painting two coats over one coat of primer on ms grill surface. etc.,complete as per the direction of the Engineer-in-charge.	Sqm.	217.00	228.60	49,606.20
					-
20	PLINTH PROTECTION WORK :				-
					-
	Making plinth protection 50 mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75 mm bed of dry brick ballast 40 mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth.	Sqm.	529.00	88.53	46,832.37
					-
21	STAINLESS STEEL STAIRCASE RAILING WITH HANDLE :				-
	Supplying , fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with balustrade of size 32mm x 32mm x 2mm @ 0.90mtr.C/C and stainless steel square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design & specification, buffing, polishing etc with cost of conveyance, taxes of all materials , labour, T & P etc. required for the complete in all respect as per the direction of Engineer-in-charge.	Rmt.	4,171.00	80.60	3,36,182.60
	FLOORING :				-
					-
22	Fixing Chequered tile in floors treads or steps and landing on 25mm thick bed of cement mortar 1 :4 (1 cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades on the tiles etc. complete as per direction of engineer in charge.	Sqm.	994.90	319.86	3,18,228.71
					-
23	Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make conforming to I.S 13755 laid on 20 mm thick cement mortar (1:4) (1 cement : 4 sand)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc.required for the work all complete as per direction of engineer in charge.				-
	Stilt floor	Sqm.	1,172.40	-	-
					-
	First floor	Sqm.	1,183.00	260.97	3,08,727.51
					-
	Second floor	Sqm.	1,194.10	260.97	3,11,624.28
					-
	Third floor	Sqm.	1,205.80	260.97	3,14,677.63
					-
	Fourth Floor	Sqm.	1,218.10	260.97	3,17,887.56

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
					-
24	Fixing vitrified tiles (600mm x 600mm) in dados skirting and risers of step on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades on the tiles etc. complete as per direction of engineer in charge.				-
					-
	Stilt floor	Sqm.	1,283.30	-	-
					-
	First floor	Sqm.	1,299.30	35.78	46,488.95
					-
	Second floor	Sqm.	1,316.10	35.78	47,090.06
					-
	Third floor	Sqm.	1,333.70	35.78	47,719.79
					-
	Fourth Floor	Sqm.	1,352.20	35.78	48,381.72
					-
					-
25	Fixing Anti-skid Ceramic tile (300mm x 300mm) in floors treads or steps and landing on 25mm thick bed of cement mortar 1 : 1 (1 cement : 1 sand) jointed with neat cement slurry mixed with pigment to match the shades on the tiles etc. complete as per direction of engineer in charge.				-
					-
	Stilt floor	Sqm.	1,054.50	-	-
					-
	First floor	Sqm.	1,065.10	26.04	27,735.20
					-
	Second floor	Sqm.	1,076.20	26.04	28,024.25
					-
	Third floor	Sqm.	1,087.90	26.04	28,328.92
					-
	Fourth Floor	Sqm.	1,100.20	26.04	28,649.21
					-
					-
26	Providing and fixing 1st quality ceramic glazed wall tiles of approved make of 5mm and size 450 mm X 300 mm conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	945.80	-	-
					-
	First floor	Sqm.	961.80	107.83	1,03,710.89
					-
	Second floor	Sqm.	978.60	107.83	1,05,522.44
					-
	Third floor	Sqm.	996.20	107.83	1,07,420.25
					-
	Fourth Floor	Sqm.	1,014.70	107.83	1,09,415.10
					-
					-
27	Providing 18 mm thick approved quality & shade polished granite slabs, and cutting to required size laid over 20 mm thick under layer of cement mortar (1:3) to masonry or concrete surfaces in skirting, dado, risers and treads of steps, counters, edges / facias complete (screwing on vertical surfaces if required) to proper level and joints filled with cement mixed with oxide matching colour in required proportion, washed, acid cleaned, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge.				-
					-
	Stilt floor	Sqm.	2,931.40	30.69	89,964.67
					-
	First floor	Sqm.	2,942.00	30.69	90,289.98
					-
	Second floor	Sqm.	2,953.10	30.69	90,630.64
					-
	Third floor	Sqm.	2,964.80	30.69	90,989.71
					-
	Fourth floor	Sqm.	2,977.10	30.69	91,367.20
					-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
28	Supplying and fixing of W.I. clamps 25 cm to 30 cm long of 35mm x 5mm size for doors including fixing in C.C. 1:3:6 with 12mm to 20mm hard stone chips or in cement mortar 1:3 including cost of all materials.	Nos.	10.77	500.00	5,385.00
					-
					-
29	Supplying, fitting & fixing 100 mm dia p.v.c rain water pipe (medium) with necessary bends, shoes, heads, etc. including cost of P.V.C pipe, clamps, nails etc. complete.	Rmt.	1,199.00	63.00	75,537.00
					-
	DOOR & WINDOW :				-
					-
30	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window /Ceosetory window s & other Frames/Chowkhat including 2 coats of Enamel paint and one coat of wood primer fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm ² , modulus of elasticity 900 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with m.s hold fast/ lugs/ SS dash fastner of required dia & length complete as per the direction of engineer-in-charge.				-
	Frame size 50 x 125 mm	Rmt.	1,054.00	487.20	5,13,508.80
					-
31	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	Sqm.	5,934.00	156.24	9,27,128.16
					-
32	Providing and fixing 30 mm thick factory made single extruded WPC (Wood polymer composite) solid plain flush door shutter of required size fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all complete as per direction of engineer in charge.	Sqm	6,154.00	50.40	3,10,161.60
					-
33	Providing and fixing of factory made approved make uPVC 2-track/3-track Sliding window (Pearl White Colour) complete, comprising uPVC multi-chambered frame of size 67mm x 54mm having uPVC roller track on top and uPVC sash of size 64mm x 47mm duly reinforced with G.I. section 1.2 mm (+/- 0.2mm), wherever required. All corners of frame and sash will be fusion welded. After placing 6mm Clear Toughened glass in the sash, uPVC glazing bead, interlock, EPDM gasket, brush will be provided including hardware, i.e., touch lock and rollers & proper drainage system shall be provided. silicon sealant shall be provided out side and inside. window will be fixed to the wall with 100mm long and 8mm dia. Fasteners and complete in all respect as per direction of Engineer-In-Charge.	Sqm	9,840.00	217.08	21,36,067.20
					-
34	Providing and fixing of factory made approved make uPVC Louver window (Pearl White colour) comprising of uPVC multi-chambered frame of size 50 mm x 42 mm, duly reinforced with 1.2 mm (+/- 0.2) thick G. I. Section. Both vertical sides of the frame, adjustable louver with 4 mm frosted glass and having one lever to adjust the glass. Window will be fixed to the wall with 100mm long and 8mm dia. Fasteners and complete in all respect as per direction of Engineer-In-Charge.	Sqm.	9,180.00	11.52	1,05,753.60
					-
35	Supplying, fabricating and fixing MS grills, railing and M.S frame madeup with M.S. square bar / round bar / flat / plate as per design and drawing including applying two coat enamel paint over a coat of red oxide primer and fixing the same to wooden door and window frames as per requirement and direction of Engineer-in-charge.	KG.	112.90	6,131.70	6,92,268.93
					-
36	AquaArm UM Waterproofing application:- Providing and application of two component polymer modified flexible cementitious waterproofing coating at a thickness of 1.5 -2.5 mm The membrane should have Elongation equal or more than: 60% Crack Bridging ability : Up to 1 mm Adhesive strength: 1.0 N/mm ² @ 28d Tensile elongation: 30% @ 20°C Shore A Hardness >85 (between 3 - 7 days) etc. as per direction of E.I.C Protective cover is in client scope.	Sqm.	540.00	535.49	2,89,164.60

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
					-
37	Providing and application of Polyurethane waterproof coating: After the primer EPW44, Single component liquid applied Elastomeric based waterproofing system AquaArm WPU1KE or equivalent should be of thickness of 1.5mm as directed by the engineer in charge. The formed membrane should have properties equal or more than at 28 days Elongation: 450 % confirming to ASTM D412 Tear resistance: 10 N confirming to ASTM D624 Shore hardness: 80 confirming to ASTM C 836 100% Modulus Elongation: 0.6 MPa(ASTM D 412) Recovery from 200% elongation: (ASTM D 412): > 80% No cracking or tearing: Extensibility after heat ageing (ASTM C 836) etc. as per direction of E.I.C Protective cover is in client scope.	Sqm.	816.00	323.81	2,64,228.96
					-
					-
	Total Civil Works				4,65,93,376.88
	P.H. WORKS				-
38	Providing all materials, labour, T&P for laying/fixing of following dia CPVC pipes SDR-11 as per IS-15778/2007 with ISI mark including fixing of required size CPVC fittings like bend, Tee, elbow, offsets etc. and the same fixed on wall or floor with holder bat clamps screw in all floor or laying in trenches including excavation of earth work in all kinds of soil & backfilling the trenches as per specification & testing the joints with required water pressure. The cost inclusive of transportation scaffolding etc. excluding GST as per specification and direction of Engineer-in-charge. Make: ASTRAL / SUPREME/ ASHRIVAD				-
(i)	15mm dia	Mtr.	180.70	128.00	23,129.60
(ii)	20mm dia	Mtr.	232.40	128.00	29,747.20
(iii)	25mm dia	Mtr.	307.60	24.00	7,382.40
(iv)	32mm dia	Mtr.	475.50	24.00	11,412.00
(v)	40mm dia	Mtr.	613.80	80.00	49,104.00
					-
39	Providing all materials, labour, T&P for laying/ fixing of following dia uPVC solvent welded pipes Sch-80 as per ASTM-D-1785 including fixing of required size uPVC Schedule-80 fittings as per ASTM D-2467 like bend, Tee, elbow, offsets etc. and the same fixed on wall or floor with holder bat clamps screw in all floors or laying in trenches including excavation of earth work in all kinds of soil & backfilling the trenches as per specification & testing the joints with required water pressure. The cost inclusive of transportation, scaffolding etc. as per specification excluding GST and direction of Engineer-in-charge. Make: ASTRAL / SUPREME/ ASHRIVAD				-
(i)	25mm dia	Mtr.	338.00	80.00	27,040.00
(ii)	32 mm dia	Mtr.	454.00	64.00	29,056.00
(iii)	40 mm dia	Mtr.	561.00	80.00	44,880.00
(iv)	50 mm dia	Mtr.	752.00	180.00	1,35,360.00
(v)	65 mm dia	Mtr.	1,260.00	30.00	37,800.00
					-
40	Providing all materials, labour, T&P for fitting & fixing of following CPVC Ball Valves(CTS Sockets) confirming to IS-15778 with ISI mark as per ASTM D-2846 in all floor & fixing with the pipes after cutting the pipes to required shape & size including wastage etc. of following nominal diameter, all complete including testing the joints with required water pressure. The cost inclusive of transportation scaffolding etc. all complete as per specification excluding GST and direction of Engineer-in-charge Make: ASTRAL / SUPREME/ ASHRIVAD				-
(i)	25 mm dia CPVC ball valve	Nos	816.00	4.00	3,264.00
(ii)	32 mm dia CPVC ball valve	Nos	1,541.00	4.00	6,164.00
(iii)	40 mm dia CPVC ball valve	Nos	2,317.00	4.00	9,268.00
(iv)	50 mm dia CPVC ball valve	Nos	3,218.00	2.00	6,436.00
(v)	65 mm dia CPVC ball valve	Nos	5,520.00	1.00	5,520.00
					-
41	Supplying all materials, labour, T&P and fitting and fixing of CI water sluice valve / butterfly valves / air valves/ non return valve of the following sizes confirming to the relevant IS specification and dimension including fixing it in position along the pipeline with supply of all required materials such as rubber insertion, nuts & bolts including cost of all materials, taxes, and duties, transportation charges from store to site etc all complete as per the direction of Engineer-in-charge.				-
	65mm dia non return valve	Nos	7,800.00	1.00	7,800.00
					-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
42	Providing all materials labour, T&P for making grooves in bricks/stone masonry walls vertically or horizontally up to required depth and width in all floor for laying of pipes and fittings up to 50mm dia, testing the joints with required water pressure and making good the damages with cement concrete 1:2:4 with 12mm size h.g.c.b.chips and finished smooth with cement mortar (1:4) to original shape including cost of all materials, curing, conveyance of all materials etc. all complete excluding GST as per specification & direction of Engineer-in-charge.	Mtr.	211.20	150.00	31,680.00
					-
43	Providing all labour,T&P for cutting holes in bricks or stone masonry wall for taking pipes in all floors and making good the damages with cement concrete 1:2:4 finished smooth with CP 1:4 to original shape including cost of all materials, curing, conveyance, duties etc. all complete as per specification excluding GST & direction of Engineer-in-charge.				-
(i)	For 15mm to 50mm dia pipe to pass in 125mm to 250mm thick wall	Nos.	50.40	80.00	4,032.00
					-
44	Providing all materials, labour, T&P for fitting and fixing white glazed vitreous china water closet (European pattern) 'P' or 'S' type of approved make as per IS-2556 with ISI mark in all floor including supply of suitable PVC wall plug and Brass screws etc. all complete including cost of PVC seat cover (solid) with hinges & rubber buffers including testing etc. all complete with all cost, and conveyance as per specification all complete excluding GST as per direction of Engineer-in-charge.				-
	European Water closet With Cistern .	Nos.	11,042.00	32.00	3,53,344.00
					-
45	Supply all materials and labour for fitting and fixing of following size white glazed vitreous china wash hand basin with pedestal of approved make in all floor of approved quality including cutting the walls & floor and making good the damages with cement concrete etc. including transportation etc. all complete excluding GST as per direction of EIC.				-
	Wash Hand Basin with Standard Pedestal of size (550x400 mm) .	Nos.	8,889.40	32.00	2,84,460.80
					-
46	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				-
	Kitchen sink with drain board				-
	600 x 450 mm bowl depth 250 mm	Nos.	6,577.60	16.00	1,05,241.60
					-
47	Providing all materials, labour, T&P for fixing of following sizes of bevelled edge mirror of 5mm thick mounted on 6mm thick AC back sheet & CP cup screw with PVC wall plugs in all floor including cost, conveyance, all materials complete as per specification excluding GST and direction of E.I.C. Jaquar (AKP-CHR-35795)				-
	600mm x 450mm size.	Nos.	2,195.60	32.00	70,259.20
					-
48	Supplying all materials, labour, T&P and fixing standard sized WALL MIXTURE of Hindware/Jaquar/Parryware of approved make etc complete including cutting the wall and making good the damages, including cost of all materials complete as per PH specification and direction of Engineering-in-charge. 15mm dia .	Each	4,697.20	32.00	1,50,310.40
					-
49	Providing all materials, labour,T&P ,fittings and fixing of different water supply (CP on Brass) fitting (Quarter Turn or as specified) as per IS specification & approved make in all floor of following sizes and specification with leak proof threaded joints with thread seal tape or any other method as required and directed including transportation etc., testing and rectification of defects after testing complete excluding GST as per direction of Engineer-in-charge.				-
(i)	15mm dia Two-Way Bibcock with wall flange.	Nos.	1,814.20	32.00	58,054.40
(ii)	15mm dia Angle Stop cock with wall flange .	Nos.	1,123.30	80.00	89,864.00
(iii)	15mm dia Concealed Stop cock with wall flange .	Nos.	1,314.00	32.00	42,048.00
(iv)	C.P. Soap Dish Holder.	Nos.	752.20	32.00	24,070.40
(v)	Health Faucet ABS SS braided hose 1.00m with CP hook.	Nos.	1,143.00	32.00	36,576.00
(vi)	15mmx50mm C.P. Extension piece	Nos.	155.00	-	-
(vii)	15mm CP Spreader	Nos.	1,288.80	-	-
(viii)	32mm dia C.P. Dome Waste coupling (Full Threaded)	Nos.	480.00	32.00	15,360.00
(ix)	CP Grating.	Nos.	279.00	48.00	13,392.00
(x)	Towel Ring.	Nos.	864.90	48.00	41,515.20
(xi)	Robe Hook.	Nos.	610.00	32.00	19,520.00
(xii)	600 mm long Towel Rail.	Nos.	1,334.90	32.00	42,716.80

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
(xiii)	15mm dia CP Bib Cock with Wall Flange	Nos.	1,814.00	-	-
(xiv)	Pillar cock	Nos.	1,575.00	32.00	50,400.00
(xv)	Swan neck Pillar cock	Nos.	1,546.00	16.00	24,736.00
(xvi)	Urinal Auto flush cock	Nos.	3,752.40	-	-
(xvii)	Division plate for Urinal of size (750 x 165 x 365)mm	No.	6,915.60	-	-
					-
50	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet etc. all complete.	No.	1,458.00	32.00	46,656.00
					-
51	Providing, fitting and fixing of C.P. brass shower arm of approved make 190 mm long heavy body with wall flange and pressure adjustable shower of approved make.	No.	1,052.00	32.00	33,664.00
					-
52	Supplying all materials, labour, T&P, fitting and fixing uPVC SWR pipes (Type-B)(Co-moulded Ring type) of approved make confirming to IS-13592/1992 with ISI marked, both below & above ground level or fixing on wall surface in all floors including transportation & scaffolding etc. all complete as per specification excluding GST & direction of the Engineer-in-charge.				-
					-
	50mm dia pipe	Mtr.	790.00	98.00	77,420.00
					-
	75mm dia pipe	Mtr.	336.00	99.00	33,264.00
					-
	110mm dia pipe	Mtr.	984.00	67.00	65,928.00
					-
	160mm dia pipe	Mtr.	1,531.10	24.00	36,746.40
					-
53	Design, Construction, Testing and Commissioning of U.G.R of 100 K.L.D (8.0 x 8.0 x 2.0) mtr. with R.C.C of 200 mm thk. in cement mortar (1:4) on 20 cm thick cement concrete bed (1:3:6) 200 mm thick R.C.C wall in cement mortar (1:4), 20 mm thick cement plaster (1:4) with a coat of neat cement punning, 2 nos. 600 dia cast iron water seal type man hole cover and frame set in 100 mm thick R.C.C. (1:2:4) cover slab, 10 nos. heavy cast iron step iron built in wall etc. including necessary earth work in excavation, refilling the sides, and disposal of excess earth as directed including provision for filling, delivery, overflow and washout piping arrangement including provision for suction chamber inside the UGR of minimum size- below the floor level of UGR etc including Construction of clear water pump house of inner size (3.875 x 4.00 x 3.00)mtr etc. all complete as per the technical specification & drawing as per the direction of Engineer-in-charge.	No.	14,70,632.82	1.00	14,70,632.82
					-
54	Gully trap (300 X 300 X 450)mm (Inside) :				-
					-
	Providing all material, labour, T&P and Constructing gully trap (Inner size 300mm x 300mm x 450mm depth) with water tight C.I. cover with frame of 300x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design, foundation concrete (1:4:8), inside & outside plaster 12mm thick with cement mortar (1:3) finished with neat cement punning, brick work with flyash bricks having crushing strength not less than 75kg/cm ² in cement mortar (1:4), cement concrete (1:2:4) finished smooth using 12mm size h.g chips, earthwork in excavation in all kinds of soil and refilling the cavity around the chamber complete as per specification.	No.	3,128.00	40.00	1,25,120.00
					-
55	Inspection chamber (750 x 750 x 500) mm (Inside) :				-
	Providing all material, labour, T&P and Constructing Inspection chamber (Inner size 750mm x 750mm x 500mm depth) with RCC precast cover (1:1½:3) with 12mm size hg chips, foundation concrete (1:4:8), inside & outside plaster 12mm thick with cement mortar (1:3) finished with neat cement punning, 12mm thick outside cement plaster (1:3), brick work with K.B bricks having crushing strength not less than 75kg/cm ² in cement mortar (1:4), cement concrete (1:2:4) finished smooth using 12mm size h.g chips, earthwork in excavation in all kinds of soil and refilling the cavity around the chamber as per specification.	No.	7,533.00	40.00	3,01,320.00
					-
56	Man hole (900 x 800 x 900) mm (Inside) :				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Providing all materials, labour, T&P required for construction of R.C.C M-25 man hole of size 900mm x 800mm x 900mm depth (inside) including machine mixing, lifting, hoisting, conveying, placing in position, mechanical consolidation, curing, de-watering (if required). The minimum thickness of RCC base slab, all side walls & roof slab shall be not less than 150mm, 150mm & 125mm (avg.) respectively. The cost shall be inclusive of rigid, levelled & plumbed centering & shuttering to required slope, alignment & size for all kinds of RCC work with steel/ ply centering materials with all bracing, ties, anchorage & supports and removing the same after required paid & placing M.S.Reinforcement HYSD bar of required dia including cutting, bending, straightening of approved quality ,earthwork in excavation in all kinds of soil and refilling the cavity around the chamber as per specification.	No.	20,410.00	3.00	61,230.00
					-
57	Supplying all materials, labour, T&P, fitting and fixing of following dia uPVC SWR (Co-moulded Ring type) fittings of approved make confirming to IS-14735 with ISI marked in all floor with transportation & requisite testing as per specification excluding GST & direction of EIC.				-
(i)	110mm x110mm P-Trap	Nos.	494.00	32.00	15,808.00
(ii)	110mmx87.5° Plane bend	Nos.	276.00	70.00	19,320.00
(iii)	110mmx87.5° door bend	Nos.	302.00	70.00	21,140.00
(iv)	110mmx45° Plane Bend	Nos.	227.00	70.00	15,890.00
(v)	110mm dia single 'Y' withoutdoor	Nos.	479.00	70.00	33,530.00
(vi)	110mm WC connector/Bend with lip ring	Nos.	360.00	32.00	11,520.00
(vii)	110mm Socket plug	Nos.	180.00	32.00	5,760.00
(viii)	110mm Pushfit Coupler	Nos.	268.00	32.00	8,576.00
					-
58	Providing ,fixing , testing and commissioning of approved make PVC vent cowl with necessary accessories etc., complete. Make-Astral,page-06				-
a)	75 mm dia (ASTRAL -M212002707)	Nos	70.90	12.00	850.80
b)	110 mm dia (ASTRAL -M212002709)	Nos	105.70	8.00	845.60
					-
59	Supplying, fixing and testing PVC muiltly floor trap with SS frame and cover 75mm dia outlet fixed on a bed of cement concrete with (Heavy duty type) etc., complete. MAKE- Astral-M252003236	NOS	252.30	48.00	12,110.40
					-
60	Supplying all materials, labour, T&P and fixing standard sized Chromium Plated Paper Holder of Hindware/Jaquar/Parryware complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws as per specification and direction of the Engineer in charge.(Hindware Cat. No.: F890003)	Each	1,381.40	32.00	44,204.80
					-
61	Supplying all materials, labour T&P and fixing OF W.C. BRUSH HOLDER of JAQUAR ACN-1143N of approved make etc complete including cost of all materials complete as per PH specification and direction of Engineering-in-charge	Each	1,838.00	48.00	88,224.00
					-
62	Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge				-
(i)	5000 Litres Capacity for drinking work Polyethylene moulded water storage tank with lid & locking arrangement as per IS-12701/1996 with ISI mark.	Nos.	78,960.00	4.00	3,15,840.00
					-
63	MANABLOCK CENTRIFUGAL TRANSFER PUMPS FOR DOMESTIC WATER TRANSFER FROM UGR TO OHR				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	GRUNDFOS CM 10-2 TWIN WITH 100LTR TANK ,consisting Each PUMP OF 1.7 HP. Centrifugal pumps Connected in parallel and mounted on common base frame and a cabinet incorporating motor protection and controller. The shaft impellers and chambers are made of stainless steel (AISI 304). The inlet and discharge parts are made of cast iron. The mechanical shaft seal is a special designed, unbalanced O-ring seal.Mainfold is made of MS CED coated.Enclosure class : IP 54, Insulation Class : F , Pipework connection is via internal Whitworth pipe threads required drive (Motor HP), having discharge capacity and pumping head as described below with all electrical accessories viz.main switch and starter, Auto on/off system , built in relay for ensuring constant and steady operation , power cable and control cable from main switch and starter with auto on-off with dry running protection to respective motors, earthing having required M.S. galvanised supporting stay/ clamp etc. complete operational. Simple control and Altration between pumps, Twin system includes suction and discharge mainfolds, isolating valves , Non- Return valves, Pressure Guage and controller CS 201(1phase).				-
					-
	1. GYM & COMMUNITY HALL				-
	No. of Pumps : 1 working +1 stand by				-
	Flow : 10 cum/hr	Nos	40,000.00	1.00	40,000.00
	Head : 10 M				-
	LPM : 66				-
					-
	2. (S+3) & (S+4)				-
	No. of Pumps : 1 working +1 stand by				-
	Flow : 10 cum/hr	Nos	60,000.00	1.00	60,000.00
	Head : 30 M				-
	LPM : 66				-
					-
	3. G+1				-
	No. of Pumps : 1 working +1 stand by				-
	Flow : 10 cum/hr	Nos	95,000.00	1.00	95,000.00
	Head : 20 M				-
	LPM : 166				-
					-
					-
	Sub Total PH Work				49,31,544.82
					-
	BORE WELL (200 MM DIA)				-
					-
63	Conducting reconnaissance survey, integrated Hydrological & Geophysical (Electrical Resistivity method) survey and selection of potential source for exploration of Ground Water including selection and recommendation of site for drilling production wells in selected area.	Job	12,600.00	1.00	12,600.00
64	Labour for drilling a perfectly vertical bore hole of a specified dia for a specified depth below ground level in alluvial soil strata by mud Rotary Rig drilling as required to suit the site condition as per the direction of Engineer-in-charge including use of own rigs with its accessories, tools and plant and consumables etc. for lowering of finished bore suitable for lowering of 200mm dia GI/PVC pipes for housing, fitted with socket and with or without well screen as per the necessity for the soft, medium, hard and boulder formation (GI/PVC casing pipes if required by the contractor to prevent collapse of over burden portion) including lower and withdrawing of casing pipe after drilling 200mm to 450mm ia in over burden portion.	Mtr	1,128.24	60.00	67,694.40
65	Providing & lowering the following size PVC pipes (ASTM) with or without slotted pipes as per the necessity from 1.00m above ground level up to required depth and fitting and fixing up in perfectly vertical position, including cutting, threading pipe and slotted pipe and supplying and fixing all jointing materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging the tube well to prevent entry of foreign materials from above. The cost inclusive of pipes, fittings, labour, consumables, POL, consumables with hire & running charges of machinaries etc. as per specification excluding GST & direction of EIC.				-
					-
(a)	Lowering of 200mm (8") dia PVC plastic pipes Sch-80 as per ASTM-D-1785/2004 upto required depth.	Mtr.	285.36	60.00	17,121.60
					-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
(b)	Cost of 200mm (8") dia PVC plastic pipes Sch-80 as per ASTM-D-1785/2004	Mtr.	2,526.36	60.00	1,51,581.60
					-
66	Cleaning and developing the tube well using their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipment , labour, all consumables, running & hire charges of machinaries etc. all complete excluding GST & direction of the Engineer-in-Charge.	Job.	10,315.56	1.00	10,315.56
					-
67	Supplying all materials, labour & tools and plant and grouting with cement slurry for sanitary sealing around the GI/PVC casing pipe up to 3mtrs below ground level to plug the bore hole including cost of cement all complete as per specification excluding GST & direction of the Engineer-in-Charge.	Mtr.	2,124.00	60.00	1,27,440.00
					-
68	Supplying all materials labour and T&P and grouting with cement slurry for Sanitary Sealing around the GI/PVC casing pipe up to 3 mtrs. Below ground level including cost of cement all complete as per the direction of Engineer-in-charge.	Nos	3,789.96	1.00	3,789.96
					-
69	Supplying all materials, labour, tools and plant and withdrawing casing pipe from the unsuccessful bore and depositing in the department store in good condition.	Mtr	156.24	60.00	9,374.40
					-
70	Supply, installation & commissioning of borewell submersible vertical multistage stainless steel complete pump and water cool motor with Stainless Steel standard EN 1.4301 (AISI 304). Motor Dia should be 4 inches and 3 phase, 50 Hz, Enclosure class IP 68 and Insulation Class B, starting method direct on-line, 2900 RPM, Motor type MS 402, Rated Voltage 3x 380-415 V. The electrical Digital pump controller panel should be operated the pump automatically with require float switch controlled sensor for filling underground tank. Digital pump controller should be LCD screen displays, phase loss protection (incoming as well as for outgoing), Individual pump overload protection, individual pump under voltage protection, dry running protection, memory function when power off and during recovery, visual and audio alarm for fault prompt, auto manual switch and Enclosure Class IP 41.				-
	Makes : GRUNDFOS/KSB/FRANKLIN				-
	Each pump Flow : 7 m3/hr,				-
	Head : 50 m,				-
	Motor Dia : 100 mm				-
	Minimum Pump Efficiency : 65%				-
	Recommended Motor of each pump : 1.5 KW , 3 Phase, 50 Hz, 2900 RPM, Water cool type.	Nos	1,08,000.00	1.00	1,08,000.00
	Digital Pump Controller Panel 1.5 KW with 1 no float switch , Relay upto 8 Amps adjustable.	Nos	30,000.00	1.00	30,000.00
	Total :				5,37,917.52
	TOTAL P.H (INTERNAL & EXTERNAL) :				54,69,462.34
					-
	INTERNAL WIRING				
1	Recessed wiring to light point / first light of group control/ call bell point/ exhaust fan point /wall fan point with 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked in 20 mm dia non-metallic PVC conduit with 6 Amp, 250 V clip in type switch ISI marked and ceiling rose ISI marked mounted on G.I modular box with face plate & cover of suitable size , with 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge.				
a)	Group A	Nos.	907	273	2,47,611.00
b)	Group B	Nos.	1351	132	1,78,332.00
c)	Group C	Nos.	1959	79	1,54,761.00
2	Recessed wiring to secondary light point looped from primary light point with 1.5sqmm FRLSH PVC insulated single core multistrand copper conductor of ISI marked with 20mm dia non-metallic PVC conduit with 1.5sqmm FRLSH PVC insulated single core multistrand copper conductor for running earth including 3 plate ISI marked Ceiling rose with all accessories & connection as per direction of Engineer-in-charge.	Nos.	595	23	13,685.00

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
3	Recessed wiring to Twin control light point with 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked in 20 mm dia non-metallic PVC conduit with 6Amp, 250 V clip in type 2way switch ISI marked and ceiling rose ISI marked mounted on G.I modular box with face plate & cover of suitable size, with 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection as per direction of Engineer-in-charge. Group C	Nos.	2918	10	29,180.00
4	Recessed wiring for 5 / 6 amp socket outlet with 6Amp, 250 V clip in type modular switch ISI marked mounted on G.I modular box with face plate & cover of suitable size including all accessories and connection on same switch board as per direction of Engineer-in-charge.	Nos.	994	88	87,472.00
5	Recessed wiring for 5 / 6 amp socket outlet with 2 x 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked in 20 mm dia non-metallic PVC conduit with 6Amp, 250 V clip in type switch ISI marked mounted on G.I modular box with face plate & cover of suitable size, with 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection on separate board as per direction of Engineer-in-charge. Group C	Nos.	1021	169	1,72,549.00
6	Recessed wiring for 3 x 6 amp socket outlet controlled by 2 nos 6Amp, 250 V clip in type switch ISI marked mounted on single G.I modular box with face plate & cover of suitable size including all accessories and connection on separate board as per direction of Engineer-in-charge.	Nos.	2132	48	1,02,336.00
7	Recessed wiring for 6 pin 16 amp socket outlet with 16Amp, 250 V clip in type switch ISI marked mounted on G.I modular box with face plate & cover of suitable size including all accessories and connection as per direction of Engineer-in-charge.	Nos.	1461	101	1,47,561.00
8	Recessed wiring for A.C/Geyser socket outlet with industrial type socket outlet, plug top and metal chained cover in sheet steel enclosure, 20A/32A SP MCB including all accessories and connection as per direction of Engineer-in-charge.	Nos.	1463	64	93,632.00
9	Supply and installation of 1/2 module Modular Box with Base plate and cover for TV Socket as per direction of Engineer-in-Charge.	Nos.	358	32	11,456.00
10	Supply, installation, testing and commissioning of TV Socket on existing Modular Box without Base plate and cover as per direction of Engineer-in-Charge.	Nos.	185	32	5,920.00
	SUBMAIN.				-
11	Recessed wiring to submain in 2 x 6 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 25 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 1 x 4 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	269	785	2,11,165.00
12	Recessed wiring to submain in 2 x 4 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 1 x 2.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	194	2460	4,77,240.00
13	Recessed wiring to submain in 2 x 2.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 1 x 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	173	4605	7,96,665.00
14	Recessed wiring to submain in 2 x 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 1 x 1.5 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	131	2402	3,14,662.00
15	Recessed wiring to submain in 2 x 10 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 25/32 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 1 x 6 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	383	150	57,450.00
16	Recessed wiring to submain in 4 x 10 sq.mm FRLSH PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 25/32 mm dia non-metallic heavy duty PVC conduit 1.6 mm thick along with 2 x 6 sq.mm FRLSH PVC insulated single core multistrand copper conductor as earth wire as required.	Mtrs	714	480	3,42,720.00
17	Supply and laying of RG6 cable for TV socket in existing conduit as directed by E-i-C.	Mtrs	99	880	87,120.00
18	Supply and laying recessed/surface Heavy duty PVC Conduit of following sizes with all accessories as directed by E-i-C.				-
(a)	20mm	Mtrs	58	880	51,040.00

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
(b)	25mm	Mtrs	69	880	60,720.00
	Distribution Boards & Panels				-
19	Supply and fixing of 4W 7 segment TPN DB of sheet steel, MCB distribution, 415 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic cover for the MCB knobs detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required with required ELCB/RCCB and TPN MCB as incomer and SPMCB C Curve as outgoings complete with bottom detachable plate for interconnections etc as required and directed by E-i-C. Note for MCB- There should be colour indication for tripping On ,Off & Trip/There should be mid trip position for toggles for electrical fault conditions.	Nos.	17699	17	3,00,883.00
20	Supply, fixing, erecting, connecting and commissioning of indoor type dust and vermin proof, sheet steel clad ready made, double door horizontal type powder coated wall mounted 12 way SPN Distribution Boards suitable for 230 V, single phase, 3 wire 50 Hz AC Supply complete with bottom detachable plate for interconnections etc as below. Incomer 1 No-40A DP MCB (10KA) Outgoings-6-32A SP MCB 10KA- 10 Nos. complete in all respect as directed and approved by E-I-C.	Nos.	8973	1	8,973.00
	PANEL				-
21	Supply, installation, testing & commissioning of floor mounting front operated front access extensible type cubicle panel totally enclosed, dust and vermin proof with IP-42 /55 protection with hinged and lockable doors. CRCA sheets including interconnections, tinned copper crimping lugs, bonding to earth and painting suitable for use at 415 V, 3phase 4 wire 50 Hz system, and to withstand a fault level of 35 KA symmetrical for 1 sec at 415 V complete as per specifications, as required and as below : All switchboards shall have provision for entry of cables from the bottom as required. All live accessible parts shall be shrouded and all equipment shall be finger touch proof. The bus bars shall be insulated with heat shrinkable sleeves. SMC/DMC shrouds and busbar supports shall be used with Indication lamp, C.T , Digital Voltmeter, Digital Ammeter and control fuse etc. complete.				-
	A) Incomer: - 320A 4P MCCB 36KA - 1 No as incomer with Electrolytic Copper Bus Bar of 4000A, RYB Indicating Lamps, Multifunction Meter, VSD as required, SP MCB's, etc. as approved by E-i-C. B) Outgoings: - 20 nos. 63A TPN MCB with provision for Three Phase Metering Unit for 20 Flats and 1 no. 40A DPMCB with Single Phase Metering unit for Common Area, 32A DP MCB 10KA - 1 No and 32A TPN MCB as spare.	set	177362	1	1,77,362.00
22	PUMP DB with 63A 4P MCB (10KA) -1 No as incomer ,32A 4P MCB 10KA-2Nos, 20A DP MCB 10KA-3 Nos as Outgoing with E.C Busbars .	set	21074	1	21,074.00
	CABLE				-
23	Supply & Laying of one number of PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of 3.5core 95 sq.mm direct in ground/surface including excavation, sand cushioning protective covering and refilling the trench or with proper clamping, etc. as required for surface.	Rmt	790	100	79,000.00
24	Supply & Laying of one number of PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of 4core 16 sq.mm direct in ground/surface including excavation, sand cushioning protective covering and refilling the trench or with proper clamping, etc. as required for surface.	Rmt	348	110	38,280.00
	END TERMINATION				-
	Supplying and making end termination with brass compression gland and aluminum lugs for following size of PVC insulated and PVC sheathed / XLPE aluminum cable of 1.1 KV as required.				-
25	3.5C x 95 sq.mm	set	650	4	2,600.00
26	4C x 16 sqmm	set	400	8	3,200.00
	EARTHING				-
27	Earthing with copper earth plate 600 mm x 600mm x 3.15 mm thick ISI marked including accessories and providing masonry with cover plate having locking arrangement and watering pipe etc with charcoal and salt as required.	Set	13530	8	1,08,240.00
28	Supplying and laying 25 mm x 6 mm CU earth strip ISI marked at 0.5 meter below ground level as strip earth electrode including soldering etc. as required.	Rmt	1041	150	1,56,150.00
29	Supplying and laying 25 mm x 6 mm CU earth strip ISI marked on surface or in recess for connection etc as required.	Rmt	1075	150	1,61,250.00
30	Providing and fixing 8 SWG CU wire on surface or in recess for loop earthing as required.	Rmt	116	300	34,800.00
	FIXTURE				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Supply, Installation, Testing and Commissioning of pre-wired fluorescent fitting / compact fluorescent fitting /LED fitting of all sizes complete with all accessories and lamp etc. directly on ceiling /wall or recessed in false ceiling , including connection with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor and earthing as required and approved by Engineer-i-Charge.				-
31	Ceiling mounted 15W LED of Recessed/Surface light.	Nos	1353	58	78,474.00
32	Ceiling/ Wall mounted type 22W LED Batten with all accessories	Nos	906	157	1,42,242.00
33	Ceiling/ Wall mounted type 10W LED Bulb with Angle holder	Nos	345	96	33,120.00
34	Ceiling/ Wall mounted type 0.5W LED Night Bulb with angle holder	Nos	230	32	7,360.00
35	Ceiling/ Wall mounted type BULK HEAD Luminaire with LED Lamp.	Nos	1562	6	9,372.00
36	45W LED Street Light fixture with required size GI clamp and accessories as required for fixing in wall.	Nos	8340	8	66,720.00
37	1200mm Ceiling Fan	Nos	3237	80	2,58,960.00
38	Step type modular fan regulator with Modular Box and Modular Cover and GI Fan Box	Nos	841	80	67,280.00
39	250mm PVC Exhaust fan with louvers	Nos	3476	48	1,66,848.00
40	Call bell	Nos	428	16	6,848.00
	SAFETY EQUIPMENTS				-
41	Supply and installation of Rubber Mats 12mm thick of size 2000mm x 1000mm x 12 mm thick Electrical tested with test certificate.	Nos	3500	1	3,500.00
42	Supply and fixing of fire buckets with angular fabricated stand to fix 4 buckets in each stand for Electrical fire protection as per standards of Electrical Inspectorate.	sets	1500	2	3,000.00
43	Supply and fixing of Co2 fire extinguisher with mounting clamps with pressure test certificate .	Nos	7500	2	15,000.00
44	Supply and fixing of shock treatement charts duly laminated along with separate colour single line diagram laminated, to be fixed in Electrical control panel room.	sets	650	1	650.00
45	Supply and fixing of first aid box with medicines complete with medicine with three years expiry date to be fixed in Electrical control panel room.	set	1500	1	1,500.00
	TOTAL INTERNAL ELECTRICAL				55,95,963.00
	Lightening Arrester				
41	Supply, Installation ,Testing & Commisioning of ESE Lightening Air Terminal early steamer emmision with OPR 60 with Radius of protection of 79 mtr in Level-1 in accordancance to NFC-17-102 standard as per the direction of E-I-C.	Nos	306976	1	3,06,976.00
42	Supply, Installation ,Testing & Commisioning of Mounting Mast of Length - 2mtr 30mm dia as per the direction of E-I-C.	Nos	24244	1	24,244.00
43	Supply, Installation ,Testing & Commisioning of GI Mounting mast of Length - 3mtr with guy wire and base plate as per the direction of E-I-C.	Nos	28395	1	28,395.00
44	Supply, Installation ,Testing & Commisioning of Lightening Flash Counter as per the direction of E-I-C.	Nos	43519	1	43,519.00
45	Supply, Installation ,Testing & Commisioning of providing maintenance free chemical earthing furse 25 kg black fill compound for lighting arrester with all cost of copper bounded rod with earth pit as per the direction of E-I-C.	Nos	29230	3	87,690.00
46	Supply, Installation ,Testing & Commisioning of 1C 70sqmm Copper Conductor as per the direction of E-I-C.	Mtr.	1034	75	77,550.00
	TOTAL LIGHTENING ARRESTER				5,68,374.00
	Substation				
	100kva Transformer with 11KV Line				
47	Construction of 11KV Overhead Line with road crossing, DP Structure with guarding, etc. as per site requirement and instruction of Site-in-Charge complete in all respect.	Mtr.	1750	1000	17,50,000.00
48	Construction of 100kva Plinth mounted Substation with all the required fittings and accessories as instructed by E-in-C.	Set	1150000	1	11,50,000.00
49	Charges of Electrical distribution department with their leassoning charges ,inspection charges for departmental engineer-in charge with all type of testing whichever required for substation area ,charging of substion with tested ok etc as required to complete the job with supplying and installation of HT/ CT opprated type LT KWH metering system with 500/5A CT range as per direction of Engg.-in-charge of concerned electricity supply company having provision for HT Measurement panel if necessary to complete the job as required.	LS	50000	1	50,000.00
50	Security Deposit to Tata Power (Electricity board) @ Rs. 4,500/KW.	Nos.	4500	80	3,60,000.00
51	6% Supervision Charges, Agrrement Charges, Processing Fees, Service Connection & Metering Charges to be deposited to Electricity Department (Tata Power).	LS	450000	1	4,50,000.00
	TOTAL Substation				37,60,000.00

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	EXTERNAL ILLUMINATION				
A	BOLLARD & STEP LIGHTING				
52	Supply & fixing of IP65 Decorative 16W Bollard LED Fixture With Die Casted and extruded Aluminum Body & poly carbonate Opal Diffuser 975mm height suitable for LED LAMP similar to K-LITE cat No. KL-4841 Vajra Bollard or equivalent With Junction Box.	Nos.	17052	12	2,04,624.00
53	Construction of RCC foundation of 425 x 300 x 300 mm size by using M25 grade RCC and Fe-550 grade steel reinforcement .The scope of work includes necessary excavation of soil and back filling after completing the foundation work, fixing the EN 8 grade J type foundation bolts and PVC /HDPE pipe inside the foundation for cable entry. The work is to be executed as per the direction of EIC and foundation drawing approved	Nos.	1850	12	22,200.00
B	CONICAL POLE & LIGHTING				-
54	Supply, installation, testing & commissioning of 7 mtr long conical lighting pole made up of MS or hot dip galvanised body similar to KP-7047 Sword Lighting Pole. The Pole shall have base Plate with provision for foundation bolt fittings, closed prewired junction box with 4P connector and 01 no. 6A SPMCB Compatible for all suitable size for cable entry complete with all materials & labour as required as per the direction of Engineer-in-Charge.	Nos.	44303	8	3,54,424.00
55	Construction of RCC foundation of 1800 x 500 x 500 mm size by using M25 brade RCC and Fe-550 grade steel reinforcement .The scope of work includes necessary excavation of soil and back filling after completing the foundation work, fixing the EN 8 grade J type foundation bolts and 63 mm dia PVC /HDPE pipe inside the foundation for cable entry. The work is to be executed as per the direction of EIC.	Nos.	7000	8	56,000.00
56	Supply, fixing & termination of Outdoor type IP66 60W Street Light Luminaire with die cast aluminium housing & polycarbonate cover similar to K-LITE Cat No. KL-4291 Waco or equivalent.	Nos.	19517	8	1,56,136.00
C	CABLING				-
57	Supplying, storing, laying, testing and commissioning of 3C X 4 Sq. mm Copper Cable 1100 Volts etc. as required. as per the direction of Engineer-in-Charge.	Mtr.	252	300	75,600.00
58	Supplying, storing, laying, testing and commissioning of 3C X 1.5 Sq. mm Copper Cable 1100 Volts etc. as required. as per the direction of Engineer-in-Charge.	Mtr.	116	106	12,296.00
59	Supplying, storing, laying, testing and commissioning of 4c x 16 Sq. mm A2XFY Al armoured Cable 1100 Volts in existing pipe etc. as required. as per the direction of Engineer-in-Charge.	Mtr.	253	240	60,720.00
60	Supplying, storing, laying, testing and commissioning of 3.5c x 35 Sq. mm A2XFY Al armoured Cable 1100 Volts in existing pipe etc. as required. as per the direction of Engineer-in-Charge.	Mtr.	438	50	21,900.00
61	Supply and laying of 40mm dia DWC pipe for laying of cable etc. as required including excavation and refilling the trench as per the direction of Engineer-in-Charge.	Mtr.	228	220	50,160.00
62	Supply and laying of 63mm dia DWC pipe for laying of cable etc. as required including excavation and refilling the trench as per the direction of Engineer-in-Charge.	Mtr.	269	40	10,760.00
D	FEEDER PILLARS				-
63	Supplying and fixing double door MS feeder pillar box with angle base providing the following component (switching acc.) inside the feeder pillar including internal wiring all. Complete for automatic , timely OFF/ON for operating of (110 nos) 60W LED lighthting fitting. i)63 A 4 pole MCB & isolat0r 1 no. ii)240 V contractor- 1 no. iii) Day dial timer (GIC)- 1 no iv) By pass switch- 1 no v) outlet Terminal - 3 nos. vii) 32 AMP FP MCB 3 NOS (1 spare) approved make complete with all materials & labour as required as per the direction of Engineer-in-Charge.	Nos.	33513	1	33,513.00
F	EARTHING				-
64	Earthing with GI earth plate 600 mm x 600mm x 6 mm thick ISI marked including accessories and providing masonry with cover plate having loccking arrangement and watering pipe etc without charcoal and salt as required.	Set	8380	4	33,520.00
65	Supplying and laying 25 mm x 5 mm G.I earth strip ISI marked on surface or in recess for connection etc as required.	Rmt	214	60	12,840.00
66	Supply, delivery & installation of GI coil earthing made out of 8 swg GI wire closely wound in shape of a helical coil of 50mm diameter with 115 numbers of turns including excavation of earthpit of size 800x 800x 1500mm in all kinds of soil, back filling the excavated pit with alternate layers of salt, charcoal around the coil with a diameter of 300mm upto 1000mm and balance by good quality soil, end termination complete as required.	Nos.	750	8	6,000.00
67	Providing and fixing 8 SWG (4 mm) dia copper wire on surface or in recess for loop earthing as required.	Rmt	116	300	34,800.00

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	TOTAL EXTERNAL ILLUMINATION				11,45,493.00
	LIFT (8 Passenger)				
68	Supply, installation, testing and commissioning of 8 passenger MRL Lift complete in all respect as approved and directed by E-i-C.	Nos.	1450000	1	14,50,000.00
	TOTAL LIFT				14,50,000.00
	Boundary Wall				-
1	EARTH WORK IN EXCAVATION				-
	Earth work in excavation of foundation trenches and column foundation and pits in all kinds of soil within an initial lift of 1.5m including dressing the sides and levelling the bed & depositing the excavated materials away from the site within an initial lead of 50m as per direction of Engineer-in-charge including cost of all labour, sundries, Tools & plants etc. complete.				-
	Ordinary/Hard Soil	cum	232.30	118.80	27,597.24
					-
2	SAND FILLING				-
	Filling foundation trenches and plinth with sweet river sand, well watered and compacted , top surface dressed and leveled to proper gradient in layers of 0.225 mtr including cost of all materials, conveyance, all taxes and royalties, loading and unloading, including cost of all labour, T&P, sundries etc. complete as per direction of the Engineer-in-charge.				-
	Foundation	cum	555.70	7.10	3,945.47
					-
3	BACK FILLING				-
	Back filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5m.				-
		cum	156.40	99.05	15,491.42
4	PLAIN CEMENT CONCRETE (1:4:8)				-
	Providing and laying Plain cement concrete of proportion (1:4:8) using 4cm size metal etc. in foundation and floors using cement, 40mm. Size crusher broken H.G.Metal and screened and washed sharp river sand for mortar of approved quality and from approved quarry including hoisting, lowering and laying concrete to the required level, ramming, watering and curing etc. complete to required levels, laid in layers not exceeding 15cm thick in each layer including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, T&P required for the work including shoring, shuttering and dewatering(if required) including hire and running charges of water pump required for the work etc. complete in all respect as directed by the Engineer-in-charge.				-
	Foundation	cum	5,197.00	0.34	1,766.98
					-
5	REINFORCED CEMENT CONCRETE M25				-
	Providing, lifting, hoisting and laying Reinforced cement concrete of M-25 Grade to Footings, retaining Wall and column. with 12mm to 20mm size black hard crusher broken granite chips of approved quality from approved quarry including mixing and compacting to proper shape and size, level and plumbs and finishing the exposed surfaces smooth, scaffolding, watering and curing for the required period including cost of all materials with taxes, royalties transportation, loading and unloading, all labour, sundries, T&P including hire & running charges of concrete mixer and vibrator etc completed as per direction of the Engineer-in-charge but excluding the cost of materials and labour for reinforcement bars for the work.				-
6.2	Plinth beam	cum	7,033.60	27.24	1,91,595.26
6.3	Column Ground Floor	cum	14,899.80	9.94	1,48,104.01
6.4	Roof Slab	cum	13,513.00	-	-
					-
7	Reinforcement				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Providing, fixing TOR Fe-500 reinforcement bars for RCC work of required diameter of approved quality with straightening, cutting, bending, binding welding and joining (if necessary) and tying the grills and placing in position as required for R.C.C. work and providing fan hooks, hoisting, lowering and laying including cost, conveyance and taxes of M.S. Rods or tor steel and binding wires of 18 to 20 gauge and labour required for the work for bending, binding and tying the grills in all heights as per the specification & direction of E-I-C. (Linear measurements will be taken & quantity will be calculated on standard weight. Weight of binding wire will not be considered for measurement.)				-
7.1	Foundation and Plinth	Qntl	8,919.00	34.36	3,06,456.84
7.2	Ground floor	Qntl	8,919.00	9.44	84,195.36
					-
8	BRICK WORK IN SUPER STRUCTURE				-
	Providin bricks masonry work using (230mmx110x0cm size) having crushing strength not less than 75Kg/Sqcm in cement mortar (1:6) make the surface wet by water before use with all necessary projections, splays cutting, circular moulding, corbelling etc as per drawings. including cost, conveyance, all taxes, royalties, loading and unloading of all materials, including cost of all labour, scaffolding, watering and curing, sundries, T&P etc. complete as per the direction of the Engineer-in-charge.				-
8.1	Foundation	cum	5,123.00	12.31	63,064.13
8.2	Superstructure -	cum	5,156.00	61.56	3,17,403.36
					-
9	Plaster				-
	Providing 16mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and level and making grooves, beads and drip coarse to give required ornamental finish as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge				-
9.1	ground floor	sqm	223.80	520.54	1,16,496.85
					-
10	Providing 12mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and level and making grooves, beads and drip coarse to give required ornamental finish as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge	sqm	157.20	479.51	75,378.97
					-
11	Painting				-
	Providing & Painting two coats with Water soluble weather coat paints of approved shade to the outside walls over a coat of primer(including cost of primer) by means of rollers to outside surface of new walls with a approved quality exterior grade putty after scraping, cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of E-I-C.				-
	Ground floor	sqm	137.10	1,000.05	1,37,106.86
	Sub-Total Boundary Wall				14,88,602.75
					-
	Guard Room				-
1	EARTH WORK IN EXCAVATION				-
	Earth work in excavation of foundation trenches and column foundation and pits in all kinds of soil within an initial lift of 1.5m including dressing the sides and levelling the bed & depositing the excavated materials away from the site within an initial lead of 50m as per direction of Engineer-in-charge including cost of all labour, sundries, Tools & plants etc. complete.				-
	Ordinary/Hard Soil	cum	232.30	40.13	9,322.20
					-
2	SAND FILLING				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Filling foundation trenches and plinth with sweet river sand, well watered and compacted , top surface dressed and leveled to proper gradient in layers of 0.225 mtr including cost of all materials, conveyance, all taxes and royalties, loading and unloading, including cost of all labour, T&P, sundries etc. complete as per direc-tion of the Engineer-in-charge.				-
	Foundation	cum	555.70	1.94	1,078.06
					-
3	BACK FILLING				-
	Back filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5m.				-
		cum	156.40	38.19	5,972.92
4	PLAIN CEMENT CONCRETE (1:4:8)				-
	Providing and laying Plain cement concrete of proportion (1:4:8) using 4cm size metal etc. in foundation and floors using cement, 40mm. Size crusher broken H.G.Metal and screened and washed sharp river sand for mortar of approved quality and from approved quarry inclduign hoisting, lowering and laying concrete to the required level, ramming,watering and curing etc. complete to required levels, laid in layers not exceeding 15cm thick in each layer including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour,T&P required for the work including shoring, shuttering and dewatering(if required) including hire and running charges of water pump required for the work etc. complete in all respect as directed by the Engineer-in-charge.				-
	Foundation	cum	5,197.00	1.30	6,756.10
					-
5	REINFORCED CEMENT CONCRETE M25				-
	Providing, lifting, hoisting and laying Reinforced cement concrete of M-25 Grade to Footings, retaining Wall and column. with 12mm to 20mm size black hard crusher broken granite chips of approved quality from approved quarry including mixing and compacting to proper shape and size, level and plumbs and finishing the exposed surfaces smooth, scaffolding, watering and curing for the required period including cost of all materials with taxes, royalties transportation, loading and unloading, all labour, sundries, T&P including hire & running charges of concrete mixer and vibrator etc completed as per direction of the Engineer-in-charge but excluding the cost of materials and labour for reinforcement bars for the work.				-
5.1	Column base footing	cum	7,033.60	6.03	42,412.61
5.2	Plinth beam	cum	7,861.00	3.60	28,299.60
5.3	Column Ground Floor	cum	14,899.80	14.78	2,20,219.04
5.4	Roof Slab	cum	13,513.00	4.20	56,754.60
					-
6	Reinforcement				-
	Providing, fixing TOR Fe-500 reinforcement bars for RCC work of required diameter of approved quality with straightening, cutting, bending, binding welding and joining (if necessary) and tying the grills and placing in position as required for R.C.C. work and providing fan hooks, hoisting, lowering and laying including cost, conveyance and taxes of M.S. Rods or tor steel and binding wires of 18 to 20 gauge and labour required for the work for bending, binding and tying the grills in all heights as per the specification & direction of E-I-C. (Linear measurements will be taken & quantity will be calculated on standard weight. Weight of binding wire will not be considered for measurement.)				-
6.1	Foundation and Plinth	Qntl	8,919.00	9.75	86,960.25
6.2	Ground floor	Qntl	8,919.00	29.64	2,64,359.16
					-
7	BRICK WORK IN SUPER STRUCTURE				-
	Providin bricks masonry work using (230mmx110x0cm size) having crushing strength not less than 75Kg/Sqcm in cement mortar (1:6) make the surface wet by water before use with all necessary projections, splays cutting, circular moulding, corbelling etc as per drawings. including cost, conveyance, all taxes, royalties, loading and unloading of all materials, including cost of all labour, scaffolding, watering and curing, sundries, T&P etc. complete as per the direction of the Engineer-in-charge.				-
7.1	Foundation	cum	5,123.00	1.20	6,147.60
7.2	Superstructure -	cum	5,156.00	8.54	44,032.24
					-
8	Plaster				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Providing 16mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and level and making grooves, beads and drip coarse to give required ornamental finish as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge				-
8.1	ground floor	sqm	223.80	56.91	12,736.46
					-
9	Providing 12mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and level and making grooves, beads and drip coarse to give required ornamental finish as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge	sqm	157.20	40.69	6,396.47
					-
10	Painting				-
	Providing & Painting two coats with Water soluble weather coat paints of approved shade to the outside walls over a coat of primer(including cost of primer) by means of rollers to outside surface of new walls with a approved quality exterior grade putty after scraping, cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of E-I-C.				-
	Ground floor	sqm	137.10	97.60	13,380.96
					-
11	Painting two coats with approved Enamel Paint on Steel surface over a coat of Red Oxide Primer including preparation of base with a approved quality & finishing the surface, smooth including all cost of materials, labour, scaffolding, T&P etc. complete as per the direction of E-I-C.				-
		sqm	217.00	25.16	5,459.72
12	Supplying and Fixing of M.S. Grills, M.S.Doors, M.S. Gate etc including cost,conveyance of all materials, priming, and labour for fitting fixing etc.complete as per the instruction of Engineer-in-Charge				-
		kg	106.70	3,311.10	3,53,294.37
	Sub-Total Guard Room				11,63,582.36
	Road Work				-
1	Surface Cutting				-
a	Earth work in excavation in hard soil or gravelly soil including dressing and levelling the bed	Cum	232.30	270.00	62,721.00
					-
2	SAND FILLING				-
	Filling foundation trenches and plinth with sweet river sand, well watered and compacted , top surface dressed and leveled to proper gradient in layers of 0.225 mtr including cost of all materials, conveyance, all taxes and royalties, loading and unloading, including cost of all labour, T&P, sundries etc. complete as per direc-tion of the Engineer-in-charge.	cum	555.70	124.50	69,184.65
					-
3	BACK FILLING				-
	Back filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5m.	cum	156.40	-	-
					-
4	Subgrade				-
	Construction of subgrade and Earthen Shoulders with approved materials obtained from borrow pits with all lift and and leads transporting to site, spreding, grading to required slope and compacting to meet requirement etc.complete as per the instruction of Engineer-in-Charge	cum	249.70	135.00	33,709.50
					-
5	GSB				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Construction of granular sub-base by providing Close graded Granular subbase Grading-III material as per table 400-1, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density complete as per the instruction of Engineer-in-Charge	cum	1650.5	126	2,07,963.00
					-
6	DLC				-
	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per Table 600.1, cement content not to be less than 150kg/cum, optimum moisture content to be determined during trial length construction , concrete strength not to be less than 10Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver and compacting with vibratory roller, finishing as per the instruction of Engineer-in-Charge	cum	3917.4	72	2,82,052.80
					-
7	M25				-
	Providing, lifting, hoisting and laying Reinforced cement concrete of M-25 Grade to road surface layer. with 12mm to 20mm size black hard crusher broken	cum	6622.1	120	7,94,652.00
					-
8	Reinforcement				-
	Providing, fixing TOR Fe-500 reinforcement bars for RCC work of required diameter of approved quality with straightening, cutting, bending, binding welding and joining (if necessary) and tying the grills and placing in position as required for R.C.C. work and providing fan hooks, hoisting, lowering and laying including cost, conveyance and taxes of M.S. Rods or tor steel and binding wires of 18 to 20 gauge and labour required for the work for bending, binding and tying the grills in all heights as per the specification & direction of E-I-C. (Linear measurements will be taken & quantity will be calculated on standard weight. Weight of binding wire will not be considered for measurement.)				-
8.1	Foundation and Plinth	Qntl	8919	72	6,42,168.00
					-
9	Kerb Stone				-
	Providin bricks masonry work using (230mmx110x0cm size) having crushing strength not less than 75Kg/Sqcm in cement mortar (1:6) make the surface wet by water before use with all necessary projections, splays cutting, circular moulding, corbelling etc as per drawings. including cost, conveyance, all taxes, royalties, loading and unloading of all materials, including cost of all labour, scaffolding, watering and curing, sundries, T&P etc. complete as per the direction of the Engineer-in-charge.				-
	Foundation	cum	5172.92	27.5	1,42,255.30
					-
10	Plaster				-
	Providing 16mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and level and making grooves, beads and drip coarse to give required ornamental finish as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge				-
	ground floor	sqm	223.8	270	60,426.00
					-
11	Painting				-
	Painting marking with adequate nos of coats on the kerb stone on both sides of road to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of oil dirt, scales, oil, grease and other foreign material etc. and lining out etc. complete as per direction of Engineer-in-Charge. New work (Two or more coats)	sqm	217	270	58,590.00
	Sub Total Road Work				23,53,722.25
	Total Boundary Wall, Guard Room & Road				50,05,907.36

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Fire Fighting				
	SUB HEAD-I (TERRACE PUMP)				
1	Supplying, installation, testing and commissioning of electric driven terrace pump suitable for automatic operation and consisting of following, complete in all respects, as required: (Terrace Pump)				
	Horizontal type, multistage, centrifugal, split casing pump of cast iron body & bronze impeller with stainless steel shaft, mechanical confirming to IS : 1520				
	Terrace pump of capacity 450 lpm(27m3/hr),35mtr head with 11 kw, 2900 RPM , 15 HP motor, with bronze LTB2 impeller material,carbon steel shaft material,cast iron FG 260 volute material, carbon/ceramic/NBR/S.S 304 seal material, insulation class F,frequency 50 hz,Enclosure type IP 55, Fitted with Gland packing,base frame,coupling, coupling guard etc. SCOPE OF SUPPLY: PUMP SET.	Set	106700	1	1,06,700.00
	MAKE- WILO,KIRLOSKAR/LUBI OR EQUIVALENT				-
2	Providing, fixing, testing & commissioning of flanged end 'y'strainer made from MS body with bottom and top removable flanges with nuts, bolts etc having filtration area at least 6 times the cross sectional area of the pipe.Make-Kartar/Zoloto/H Sarker/Eq.				-
a)	80 mm dia	Each	9636	1	9,636.00
					-
3	Providing, fixing, testing & commissioning of C.I. Butterfly valve conforming to IS : 13095 with nut, bolts and washers complete . [PN -1.6 rating (16kg/cm2)]Make-Kartar/Zoloto/H Sarker/Eq.				-
a)	80 mm dia	Each	6990	2	13,980.00
					-
4	Providing, fixing, testing & commissioning of C.I. dual plated Non-return valve [PN 1.6 Rating (16kg/cm2] complete 2 nos. matching flanges, rubber insertion, with nuts, bolts and washers etc of following sizes .Make-Kartar/Zoloto/H Sarker/Eq.				-
a)	80 mm dia	Each	6508.5	1	6,508.50
					-
5	Providing & fixing dial type (150 mm dia) pressure gauge with isolation ball valve suitable for working pressure of 250 PSI cost shall be of inclusive of providing any short pieces, nipples, elbows etc as required. having calibration of 0-15 Kg/cm2.Make-H.guru/Emerald/Fiebig/Equivalent	Each	1450	1	1,450.00
					-
6	Providing, fixing, testing & commissioning of resilient rubber lined single arch vibration eliminators suitable for raw water up to 45oC temperature, working pressure 10.0 Kg/cm2 and test pressure 20 Kg/cm2 for :-				-
a)	80 mm dia	Each	14500	2	29,000.00
					-
7	Supply,Providing & fixing Pressure Switch the most commonly used fluid control components of Aluminum encloser with storage temprature 40 to 180°F (-40 to 82°C) along with ambient temprature 0 to 160°F (-18 to 71°C),set point shifts less than 1% of range for a 50°F (28°C) ambient temperature change. Unit will operate down to -40°F (-40°C) but with reduced repeatability. Maximum media temperature 200°F (93°C), Shock Set point repeats after 50 G, 10 millisecond duration. Switch output One SPDT including seven electrical terminations; Refer to 'How to Order' and vibration set point repeats after 10 G, 5-500 CPS. Make-Honeywell/Danfoss/Jhonson controls.	Each	5100	1	5,100.00
					-
8	Providing, fixing, testing & commissioning of Ball Valve.Make-Kartar/Zoloto/H Sarker/Eq.				-
	20 mm	Each	1350	3	4,050.00
					-
9	Supply & installation testing & commissioning of air release valve with all fottings & isolation valve.	Each	2258.3125	1	2,258.31
					-
10	Fixing, testing and commissioning of heavy class MS pipe, IS : 1239 marked with all necessary fittings like tees, elbows, flanges, reducers, gaskets, nuts and bolts etc. welded or screwed joints as required including fixing the pipe.Make-Tata/Zindal/Sail/Eq				-
a)	80 mm dia	Metre	1558.48	120	1,87,017.60
b)	25 mm dia	Metre	868.94	30	26,068.20
					-
	ELECTRICAL WORKS:				-
11	Sitc of Terrace Pump Controller				-

Sl. No	Description of the work	Unit	Rate	BOQ Qty	Total Amount (In Rs.)
	Design, manufacture, supply, installation, testing and commissioning of following MV switchgear panels suitable for 415 V, 3 phase, 4 wire, 50 Hz power distribution system. The panel shall be Indoor, free standing, floor mounting/wall mounted, sheet metal clad, cubicle.				-
	All MCCBs shall be provided with magnetic & adjustable thermal releases for short circuit & overload protection with front drive kit (rotary operating handle).Make-c&s/l&t/crompton	Each	15500	1	15,500.00
					-
12	Supply, installation, testing & commissioning of following sizes of 1100 V grade XLPE insulated, extruded PVC inner & outer sheathed, Aluminium, armoured cables, including cable trays /supports as per site conditions.Make-Polycab/Kei/Crystal/Eq.				-
					-
12.1	4C x10 Sqmm	RM	359.607875	100	35,960.79
					-
	Cable Tray:				-
13	Earthing Strip :				-
	Supply, Installation, Testing & Commissioning of the following size of GI strip/wire clamped to wall, cable trays complete as required including interconnection between lengths at joints, all fixing accessories saddles, clamps etc. and other fixing hardware.				-
13.1	8 SWG Copper Wire	RM	116	100	11,600.00
					-
					-
14	Providing, fixing, testing & commissioning of Wall mounting swinging type(COMPACT TYPE) first aid fire hose reel with drum, hanging bracket, 30 Mtr. length x 20 mm dia heavy duty high pressure hose reel tubing as per IS: 444 with PVC shut off nozzle having 6.5 mm dia orifice. The hose reel shall be conforming to IS : 884-1985. Rate shall include 25 mm dia M.S. pipe (heavy class) connection from Riser to hose reel, sockets, nipples, elbows and ball valve (25 mm dia). Drum shall be fixed on adjoining wall by means of 120 mm x 100 mm long fasteners, bolts and nuts including painting.Make-KARTAR, Safex, Fireshield, Safe Guard	Each	7178.645	6	43,071.87
					-
15	Providing, fixing, testing & commissioning of Ball Valve.Make-Kartar/Zoloto/H Sarker/Eq.				-
	25 mm	Each	1498.176875	6	8,989.06
16	Supply, installation, testing and commissioning of Fire Brigade inlet connection with provision for two male instantaneous coupling fabricated out of 100 mm dia. approved make heavy class MS pipe with non-return valve, Butterfly valve for fire fighting system including making connection by providing necessary piping & fittings to the fire storage tank, fire fighting wet riser, sprinkler system painting the same with 3 coats of enamel paint over a coat of Zinc Chromate primer all complete as per drawings, specifications. Make-Minimax, Safex, Fireshield, Kartar.				-
	a) Two way	Nos	16049.6875	1	16,049.69
					-
	SUB HEAD-III (FIRE EXTINGUISHER)				-
17	Providing and fixing ABC type fire extinguishers consisting of welded M.S cylindrical body, squeeze lever discharge valve fitted with pressure indicating gauge internal discharge tube, 30cms long high pressure discharge hose, discharge nozzle, suspension bracket, conforming to IS finished externally with red enamel paint and fixed to wall with brackets complete with internal charge.Make-Minimax, Safex, Fireshield, Safe Guard				-
	Capacity 6 kg	SET	5832.225	12	69,986.70
18	Providing and fixing carbon-di-oxide type fire extinguishers consisting of welded M.S cylindrical body, squeeze lever discharge valve fitted with pressure indicating gauge internal discharge tube, 30cms long high pressure discharge hose, discharge nozzle, suspension bracket, conforming to IS : 2878 finished externally with red enamel paint and fixed to wall with brackets complete with internal charge . Make-Minimax/Safex/Fireshield/Safe Guard/Eq				-
	Capacity 4.5kg	SET	10185.2625	12	1,22,223.15
	SUB HEAD-IV(SIGNAGE SYSTEM)				-
19	For FIRE EXIT(12" X 6")	Nos	750	1	750.00
20	For FIRE HOSE REEL(16" X 6")	Nos	700	6	4,200.00
21	For Stair case (12"x6")	Nos	700	8	5,600.00
22	FIRE EXTINGUISHER (12"X6")	Nos	650	24	15,600.00
	Total Fire Fighting				7,41,299.87