

Sl. No.	Item Description/ Component Details	Quantity	Units	RATE In Figures (On Lumpsum Component basis) To be entered by the Bidder in Rs.	TOTAL AMOUNT in Rs.
1	2	4	5	13	53
1	Workman Housing Complex (BQ Area)				
1.01	Residential Blocks (Stilt+6) - Total 08 Towers (Tentative Plinth Area of Residential Blocks (8 * 3419.38 = 27,355 Sq.m) Design including detailed topographical survey, geotechnical investigation, preparation of drawings for Structural, MEP (services & infrastructure required), shop drawings & any other design/drawing as indicated in tender document, proof checking/vetting of drawings & Construction of RCC framed Structure of "Residential Block (Stilt+6 storeys) including all related services as per Tender Document including jungle clearance, removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, anti-termite treatment, sand filling in plinth, centering & shuttering works, RCC works, CC works, Masonry work, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., flooring, cladding, skirting, dado, sill, stone works, all finishing work including Internal & External Plaster, plaster drip course/groove, painting, door-window-ventilators of all types including their fittings and fixtures, curtain rods as required, Aluminium & glass work of all types including fittings and fixtures, wooden wardrobe including fittings & fixtures, kitchen with granite counter, shelves (overhead & under counter) and shutter as required with all fittings and fixtures, steel work, SS railings & invisible grill work including fittings and fixtures, all services like water supply, sanitary, drainage etc. including their fittings, fixtures & installations, interior work like false ceiling, all toilet & sanitary works including fittings and fixtures, installations, water proofing, over head tank for domestic,flushing and fire fighting water, plinth protection work all around the building, water-supply system, entry ramps to buildings etc. complete in all respect. All E&M services, rising mains, 02 nos. lifts per tower (one lift for 15 passenger & one lift for 15 passenger cum stretcher), installations of Internal & External Electrifications work, Fire fighting, signages,Fire Alarm System & PA, IP Based CCTV security surveillance system, Solar PV Generation Power Plant, UPS, Pressurized Ventilation for lifts, LT cables, LT Panels, emergency panels, Gas supply system including gas flow meter, smart meters for electricity & water as per requirement, External lighting & EV charging system, provision for internet connectivity & DTH connection to individual flats (For internet connectivity only condulting from LV shaft to drawing/living/dining rooms to be provided) etc., civil, electrical, mechanical external services connection, all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of residential building towers. Obtaining and submission of all necessary statutory approvals (pre-construction to post construction) from all local authorities/boards like obtaining fire, lifts license, electrical clearance etc., obtaining occupancy certificate / completion certificate from all concerned local bodies or any authorities, consent to operate (CTO), water connection, electric connection, fulfillment of GRIHA 3 STAR rating/certification etc. including preparation & submission of all 'As-built drawings' all complete as per scope of work, conditions and other details provided in NIT/Tender document and as per direction of Engineer-in-Charge. All work to be executed as per approved Architectural, MEP, shop, GFC drawings, tender conditions by incorporating stipulated specifications, design basis report, scope of work, schedule of finishes, conditions and other details stipulated in NIT/Tender document including all works whether specifically mentioned or not, but require to fulfill the intended purpose with all incidental works to complete and making the facilities functional all complete as per direction of Engineer-in-Charge. The work is to be executed for all residential blocks. Defect liability period of 24 months as stipulated in NIT/Tender Document including Operation & Maintenance of electromechanical equipments is included in the proposed works and rates to be quoted accordingly.	27355.00	Sqm		0.00
1.02	Guest House (G+3) (Tentative Plinth Area : 1990 Sq.m) Design including detailed topographical survey, geotechnical investigation, preparation of drawings for Structural, MEP (services & infrastructure required), shop drawings & any other design/drawing as indicated in tender document, proof checking/vetting of drawings & Construction of RCC framed Structure of "Guest House (G+3 Storeys)" including all related services as per Tender Document including jungle clearance, removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, anti-termite treatment, sand filling in plinth, centering & shuttering works, RCC works, CC works, Masonry work, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., flooring, cladding, skirting, dado, sill, stone works, all finishing work including Internal & External Plaster, painting, door-window-ventilators of all types including their fittings and fixtures, curtain rods as required, Aluminium & glass work of all types including fittings and fixtures, toughened glass frame & partition with all fittings & fixtures, Kitchen to be developed as a commercial and modular facility to cater to operational efficiency and modern standards, steel work, SS railing work including fittings and fixtures, all services like water supply, sanitary, drainage etc. including their fittings, fixtures & installations, interior work like false ceiling, all toilet & sanitary works including fittings and fixtures, installations, water proofing, over head tank for domestic,flushing and fire fighting water, plinth protection work all around the building, water-supply system, entry ramps & steps to building etc. complete in all respect. All E&M services, rising mains, 01 nos. lifts (15 passenger cum stretcher), installations of Internal & External Electrifications work, Energy efficient split Air Conditioning System, Fire fighting, signages,Fire Alarm System & PA, IP Based CCTV security surveillance system, IP based EPABX system & LAN system, Solar PV Generation Power Plant, UPS, Pressurized Ventilation for lifts, Mechanical ventilation for toilets, LT cables, LT Panels, emergency panels, Gas supply system including gas flow meter, smart meters for electricity & water as per requirement, External lighting etc., civil, electrical, mechanical external services connection, all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of Guest House. Obtaining and submission of all necessary statutory approvals (pre-construction to post construction) from all local authorities like obtaining fire, lifts license, electrical clearance etc., obtaining occupancy certificate / completion certificate from all concerned local bodies or any authorities, consent to operate (CTO), water connection, electric connection, fulfillment of GRIHA 3 STAR rating/certification etc. including preparation & submission of all 'As-built drawings' as per scope of work, conditions and other details provided in NIT/Tender document and as per direction of Engineer-in-Charge. All work to be executed as per approved Architectural, MEP, shop, GFC drawings, tender conditions by incorporating stipulated specifications, design basis report, scope of work, schedule of finishes, conditions and other details stipulated in NIT/Tender document including all works whether specifically mentioned or not, but require to fulfill the intended purpose with all incidental works to complete and making the facilities functional all complete as per direction of Engineer-in-Charge. Defect liability period of 24 months as stipulated in NIT/Tender Document including Operation & Maintenance of electromechanical equipments is included in the proposed works and rates to be quoted accordingly.	1990.00	Sqm		0.00
1.03	Community Centre (G+1) (Tentative Plinth Area: 1035 Sq.m) Design including detailed topographical survey, geotechnical investigation, preparation of drawings for Structural, MEP (services & infrastructure required), shop drawings & any other design/drawing as indicated in tender document, proof checking/vetting of drawings & Construction of RCC framed Structure of "Community Centre (G+1 Storeys) including all related services as per Tender Document including jungle clearance,removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, anti-termite treatment, sand filling in plinth, centering & shuttering works, RCC works, CC works, Masonry work, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., flooring, cladding, skirting, dado, sill, stone works, all finishing work including Internal & External Plaster, painting, door-window-ventilators of all types including their fittings and fixtures, Aluminium & glass work of all types including fittings and fixtures, toughened glass frame & partition with all fittings & fixtures, steel work, SS railing work, rolling shutter work including fittings and fixtures, all services like water supply, sanitary, drainage etc. including their fittings, fixtures & installations, interior work like false ceiling, wooden flooring as required, all toilet & sanitary works including fittings and fixtures, installations, water proofing, over head tank for domestic,flushing and fire fighting water, plinth protection work all around the building, water-supply system, entry ramps/steps to building etc. complete in all respect. All E&M services, installations of Internal & External Electrifications work, Energy efficient VRV/VRF air-conditioning system, Fire fighting, signages, Fire Alarm System & PA, IP Based CCTV security surveillance system, IP based EPABX system & LAN system, Solar PV Generation Power Plant, UPS, Mechanical ventilation system, LT cables, LT Panels, emergency panels, smart meters for electricity & water as per requirement, External lighting etc., civil, electrical, mechanical external services connection, all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of Community Centre. Obtaining and submission of all necessary statutory approvals (pre-construction to post construction) from all local authorities like obtaining fire, electrical clearance etc., obtaining occupancy certificate / completion certificate from all concerned local bodies or any authorities, consent to operate (CTO), water connection, electric connection, fulfillment of GRIHA 3 STAR rating/certification etc. including preparation & submission of all 'As-built drawings' as per scope of work, conditions and other details provided in NIT/Tender document and as per direction of Engineer-in-Charge. All work to be executed as per approved Architectural, MEP, shop, GFC drawings, tender conditions by incorporating stipulated specifications, design basis report, scope of work, schedule of finishes, conditions and other details stipulated in NIT/Tender document including all works whether specifically mentioned or not, but require to fulfill the intended purpose with all incidental works to complete and making the facilities functional all complete as per direction of Engineer-in-Charge. Defect liability period of 24 months as stipulated in NIT/Tender Document including Operation & Maintenance of electromechanical equipments is included in the proposed works and rates to be quoted accordingly.	1035.00	Sqm		0.00

Sl. No.	Item Description/ Component Details	Quantity	Units	RATE In Figures (On Lumpsum Component basis) To be entered by the Bidder in Rs.	TOTAL AMOUNT in Rs.
1	2	4	5	13	53
1.04	SUB STATION & PANEL ROOM/Electrical Sub-Station (Single Storey) (Tentative Plinth Area: 368 Sq.m) Design including detailed topographical survey, geotechnical investigation, preparation of drawings for Structural, MEP (services & infrastructure required), shop drawings & any other design/drawing as indicated in tender document, proof checking/vetting of drawings & Construction of "SUB STATION & PANEL ROOM (Single Storey)" including all related services as per Tender Document including jungle clearance, removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, anti-termite treatment, sand filling in plinth, centering & shuttering works, RCC works, CC works, Masonry work, trenching works, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., flooring, skirting, sill, stone works, all finishing work including Internal & External Plaster, plaster drip course/groove, painting, door-window-ventilators of all types including their fittings and fixtures, Aluminium & glass work of all types including fittings and fixtures, steel work, chequered plates for internal trench, rolling shutter works with all fittings & fixtures, services like drainage including their fittings, fixtures & installations, terrace water proofing, plinth protection work all around the building, external area development for placement of DG set like foundation, external trenching with precast cover & connection to internal trenching, chain link fencing with gates for surrounding the area of DG sets, entry ramps/steps to buildings etc. complete in all respect. Planning, Design, supply, Installation, testing & commissioning of 11KV High Voltage Panels with 30 min battery power back up for control circuit, 11/433KV Dry type step down Transformers, complete with associated auxiliaries as specified in technical specifications. High voltage cables for inter-connection between the H.V. panel and transformers including end terminations. M.V. Panels, Bus trunking (sandwich type) cables for inter-connection between transformer's M.V. terminals and the M.V. Panel as specified. Automatic Power Factor Improvement Panel if required, active harmonic filters, TVSS (transient voltage suppression system), SPD (surge protection system), Earthing system for entire substation equipments. Safety Equipments, framed instruction chart & SLDs & fire suppression system as per technical specifications. Emergency M.V. Panel, DG set with AMF panel, MS structure for DG exhaust, cables for inter connection between DG set to AMF panel, Main LT panel to AMF panel & AMF panel to Emergency panel, LT Power & Control cables including end terminations. External Electrical service connections, all electrical equipments foundations, Internal & External electrical works, fire detection and Alarm system etc. complete as required. Miscellaneous items required for successful testing and commissioning of substation equipments as per direction of Engineer-In-Charge and all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of Sub-station & Panel Room. Obtaining and submission of all necessary statutory approvals (pre-construction to post construction) from all local authorities like obtaining fire, electrical clearance etc., obtaining occupancy certificate / completion certificate, CEA certificate from all concerned local bodies or any authorities, consent to operate (CTO), water connection, electric connection, fulfillment of GRIHA 3 STAR rating/certification etc. including preparation & submission of all 'As-built drawings' as per scope of work, conditions and other details provided in NIT/Tender document and as per direction of Engineer-in-Charge. All work to be executed as per approved Architectural, MEP, shop, GFC drawings, tender conditions by incorporating stipulated specifications, design basis report, scope of work, schedule of finishes, conditions and other details stipulated in NIT/Tender document including all works whether specifically mentioned or not, but require to fulfill the intended purpose with all incidental works to complete and making the facilities functional all complete as per direction of Engineer-in-Charge. Defect liability period of 24 months as stipulated in NIT/Tender Document including Operation & Maintenance of electromechanical equipments is included in the proposed works and rates to be quoted accordingly.	368.00	Sqm		0.00
1.05	External development works including other ancillary infrastructure - (Overall Ground Area: tentatively about 24,675 Sqm) The overall work is mentioned as under: Design including detailed topographical survey, geotechnical investigation, preparation of drawings for Structural, MEP (services & infrastructure required), shop drawings & any other design/drawing as indicated in tender document, proof checking/vetting of drawings & construction of External development works & other ancillary infrastructure, mentioned as under, including all related services as per Tender Document with brief details as under: (a) Guard rooms with toilet - 02 Nos. (Single Storey) including Control room for Main Gate - Tentative Plinth Area: 35 Sq.m x 2= 70 Sqm Security hut (Single Storey) - Tentative Plinth Area: 6 Sqm RCC framed Structure of "Guard room - 02 nos. (Single storey) & Security Hut - 01 no. (Single Storey) including jungle clearance,removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, anti-termite treatment, sand filling in plinth, centering & shuttering works, RCC works, CC works, Masonry work, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., flooring, skirting, dado, sill, stone works, all finishing work including Internal & External Plaster, painting, door-window-ventilators of all types including their fittings and fixtures, Aluminium & glass work of all types including fittings and fixtures, steel work, all services like water supply, sanitary, drainage etc. including their installations, all toilet & sanitary works including fittings and fixtures, installations, water proofing work on terrace, over head polyethylene water storage tank for domestic & flushing water, plinth protection work all around the building, water-supply system, etc. complete in all respect. All E&M services, installations of Internal & External Electrifications work, signages, CCTV system, LED display, IP based EPABX system & LAN system, Rack & interconnections, UPS, DB & MCB, External lighting, 02 nos. 2TR split AC with timer switch etc., civil, electrical, mechanical external services connection, all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of Guard Rooms/control room. For security hut - All E&M services, installations of Internal & External Electrifications work, signages, electrical, mechanical external services connection etc. with integrating all services. (b) Boundary Wall (3.6 m Height from outside road level) having Length approx. 768 m (along the plot boundary) as per drawing/site layout including gates & entrance structure RCC framed structure of Boundary wall & entrance structure with providing & fixing MS gates including jungle clearance,removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure if any, centering & shuttering works, RCC works, CC works, Masonry work, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., weep holes with uPVC pipes, all finishing (External Plaster), painting, expansion joint, steel works, concertina coil fencing works, providing and fixing MS gates etc. complete in all respect. (c) Parking shed - Cantilever type Jungle clearance, removal of trees, all cutting and filling in earthwork (to desired levels as per drawings) as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts, demolition of existing structure, if any, centering & shuttering works, RCC works, CC works, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., providing, fabrication & erection of structural steel frame work with fixing to RCC pedestal suitably and roofing with profiled GS sheet, priming and painting of steel works complete in all respect. (d) Other External development works includes levelling work and raising original ground level to desired levels (as per drawings), internal roads & on-street parking areas of the housing complex & external road (connectivity to adjacent colony road near house no. TD+44 of TD+ housing from Entry/Exit-2 & connectivity to existing public road from Entry/Exit-1), footpaths, culverts (Pipe/slab/box as per site requirement) for crossing existing drains, Pump room & UGWT, signages and road/parking marking etc., Trenches for services, External water supply system (for domestic, flushing, garden irrigation), Storm water drainage (surface and roof water), Rain water harvesting system, External Sewerage system, STP - Sewerage Treatment plant (including all civil, electrical & mechanical works), Horticulture, Landscaping & Electrical, Mechanical Works etc. as per drawings Jungle clearance,removal of trees, levelling of site & raising original ground level to desired levels (as per drawings) including all cutting and filling in earthwork as required including disposal of unsuitable/excess earth and supply of suitable/desired filling material for all leads and lifts to achieve the desired levels, demolition of existing structure, if any, anti-termite treatment, centering & shuttering works, RCC works, CC works, Masonry works, laying concrete with all precautions in or under water/liquid mud with pumping/bailing out water, removing slush etc., road (internal & external), on-street parking areas, signages and road/parking markings etc., paver, footpath & ramps, culverts, steel, SS railing works with all fittings & fixtures, external water-supply, sewerage system, drainage system, rain water harvesting system with all trenching/excavation, bed preparation, backfilling, RCC, CC works, precast covers, pipe laying, connections to main/city services, manholes/chambers/traps/drains with required covers etc., valves and other fitting & fixtures, UG Tank with Pump Room including basement with all works (RCC, CC, plaster, painting, waterproofing, flooring, railing etc.), Supply, installation of STP including all civil works, plant room as per requirement, tertiary treatment, treated water tank, ultra filtration unit such that water is made reusable for flushing etc. for the campus including testing & commissioning of all works/utility services. Electrical & Mechanical Works includes street lights & poles, solar street lights, bollard lights & post top lights, gate lights, street light feeder pillars, LT cable & its laying, interconnections of street light poles, foundations of all equipments/poles, CCTV camera with poles & accessories, LAN, IP based EPABX system, POE switches, OFC cable, CAT 6A cable, patch cord, face plate, core switch, access switch, rack, patch cord, OFC & CAT 6A cable, fire-fighting, laying with trenching, bed preparation, Gas pipe line system, smart meters for water & electricity as required including all works.	24675.00	Sqm		0.00

Sl. No.	Item Description/ Component Details	Quantity	Units	RATE In Figures (On Lumpsum Component basis) To be entered by the Bidder in Rs.	TOTAL AMOUNT in Rs.
1	2	4	5	13	53
	The works mentioned under (a) to (d) as above to be completed in all respects including civil, electrical, mechanical external services connection, all internal and external electrification, mechanical, plumbing works and integrating all internal & external services pertaining to Civil, E&M etc. of External development works & other ancillary infrastructure. Obtaining and submission of all necessary statutory approvals (pre-construction to post construction) from all local authorities like obtaining fire, electrical clearance etc., obtaining occupancy certificate / completion certificate from all concerned local bodies or any authorities, consent to operate (CTO), water connection, electric connection, fulfilment of GRIHA 3 STAR rating/certification etc. including preparation & submission of all 'As-built drawings' as per scope of work, conditions and other details provided in NIT/Tender document and as per direction of Engineer-in-Charge. All work to be executed as per approved Architectural, MEP, shop, GFC drawings, tender conditions by incorporating stipulated specifications, design basis report, scope of work, schedule of finishes, conditions and other details stipulated in NIT/Tender document including all works whether specifically mentioned or not, but require to fulfill the intended purpose with all incidental works to complete and making the facilities functional all complete as per direction of Engineer-in-Charge. Defect liability period of 24 months as stipulated in NIT/Tender Document including Operation & Maintenance of electromechanical equipments is included in the proposed works and rates to be quoted accordingly.				
Total in Figures					0.00