

SECTION 6D

SCHEDULE
OF
FINISHES

CIVIL, SANITARY & PLUMBING
WORKS

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
RESIDENTIAL BLOCKS									
1	Stilt Floor (Two-Wheeler Parking & Multi-purpose area)	25mm thk. Kota Stone	100mm high Kota Stone (20 mm thick) skirting all around including columns in between	Internal walls to be painted with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	-	-	-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	Fire Control Room in Stilt	25mm thk. Kota Stone	100mm high Kota Stone (20 mm thick) skirting all around	Internal & external of walls painted with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
3	Passage/Corridor/Lift Lobby	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre-moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) (100 mm high) all around excluding Lift façade. 18 mm thick mirror polished granite on Lift Façade (facia & jambs) upto Ceiling Height.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	-	-	-		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
4	Staircase on all floors	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre-moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	-	-	Powder Coated (minimum 50 micron coating) Aluminium Sliding/Fixed window with 5mm clear float Glass glazing over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster. Note: 6 mm plaster has to be done on waist slab (bottom & side) and landing slab.
5	Bedrooms (M. Bedroom & Bed room-2)	Polished Glazed Vitrified Tile of size 600 x 600 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over 2mm thick POP above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter and 120X60 mm for double shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges. The balcony door to have double shutter i.e. one 30 mm thick shutter of 2nd class teak wood with SS 304 fly proof Mesh panels fixed with 2nd class teak wood beading as required and another 35 mm thick flush door shutter as mentioned above. The wood work to be painted with wood primer and synthetic enamel paint all around.	2nd class teak wood frame (minimum size 120X60 mm) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint all around. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.	30 mm thick casement window shutters. Shutter panels of 2nd class teak wood with 5 mm thick float glass glazing and same number shutters with 2nd class teak wood panels with SS 304 fly proof mesh. Panelling fixed with 2nd class teak wood beading as required. The wood work will be painted with wood primer and synthetic enamel paint all around.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
RESIDENTIAL BLOCKS									
6	Living/Dining	Polished Glazed Vitrified Tile of size 600 x 600 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size. 2.1m height Dado of Vitrified tile size 600x600mm or appropriate size on wash basin wall (front & sides).	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over 2mm thick POP above 12 mm cement plaster.	Door - Main Entrance & Balcony 2nd class teak wood frame (minimum size 120X60 mm for double shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	Door - Main Entrance & Balcony 35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges. Wire gauge panels shutter 30 mm thick of 2nd class teak wood with SS 304 fly proof Mesh panels fixed with 2nd class teak wood beading as required. The wood work to be painted with wood primer and synthetic enamel paint all around. Note: Magic Eye to be provided on flush door shutter of Main Entrance to unit.	Balcony 2nd class teak wood frame (minimum size 120X60 mm) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint all around. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.	30 mm thick casement window shutters. Shutter panels of 2nd class teak wood with 5 mm thick float glass glazing and same number of shutters with 2nd class teak wood panels with SS 304 fly proof mesh. Panelling fixed with 2nd class teak wood beading as required. The wood work will be painted with wood primer and synthetic enamel paint all around.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
7	Toilets (C. Toilet & A. Toilet)	Rectified Anti-skid Ceramic Tile of size 300 x 300 mm including grouting the joints.	Dado: Ceramic Tiles of size 300 x 450 mm up to False Ceiling Level with decorative band at certain intervals of appropriate size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 30 mm thk. flush Door shutter having min. density 650 Kg/cum.	Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.		15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles.
8	Kitchen	Matt/Antiskid finish Glazed Vitrified Tiles of size 600 x 600 mm finished with matching grout.	Vitrified Tile upto 2.1m height of 600 x 600 mm or appropriate size as per approved drawings.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter and fixed glazing above including Exhaust fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
9	Study Room	Polished Glazed Vitrified Tile of size 600 x 600 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over 2mm thick POP above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
10	Balcony	Matt/Antiskid finish Glazed Vitrified Tiles of size 600 x 600 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 18mm cement plaster in two coats.	Mentioned in Sr. no. 5 & 6 above				Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 6 mm cement plaster.
11	Mumty	18 mm Thk. Polished Granite- Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre-moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Internal walls painted with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS door with MS frame finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
RESIDENTIAL BLOCKS									
12	All External walls including Parapet (including top & terrace slab side of parapet), terrace slab side of Lift overhead, shafts, mummy, overhead tanks at Terrace etc.	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
13	Shafts (Lift, Services - Electrical, Fire, LV, Plumbing)	Waterproofing in Lift pit as per specifications		White washing with lime over 12mm cement plaster.	Doors of Electrical shaft to be as per NBC and CPWD specifications with latest amendment. Door for LV shaft is MS frame & shutter with ventilator arrangement as/drawing. Door of FHC shaft as per applicable guidelines/specifications.		For Plumbing shafts - Powder Coated (minimum 50 micron coating) Aluminium frame & Shutter with Louvers		-
14	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							
15	Balcony Railing	230 high Concrete wall/beam with 970mm high Stainless Steel railing of grade 304. 18mm thick gang saw cut granite of approved colour & shade, edges rounded and projecting 12mm from finished wall surface at balcony sill. Invisible grill as per specifications and drawing fixed on 230 high concrete wall/beam.							
16	Accessible & Non-accessible terrace (like terrace slab of towers, mummy, lift overhead, Overhead water tank, shafts (if required))	Selfhealing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							
17	External Entry Ramp to lift lobby & stilt Parking area	To lift Lobby - 60 mm thick precast cement concrete paver block (M 30) & Stainless steel grade 304 railing & tactile flooring as per specifications. To stilt parking area - RCC with broom finish							
18	Kitchen Counter platform, shelves, partitions, drop, facias	Gang saw cut granite; edges rounded - mirror polished, pre moulded and pre polished, machine cut granite as per specifications/approved drawings. For fixing shelves/partitions/counter with wall suitable bracket arrangement as per specifications/approved drawings.							
19	Wardrobe & Kitchen Cabinets shutters	Factory pressed BWP grade marine ply including 2mm thick PVC edge banding tape to be used with other fittings & fixturers as per approved drawings & specifications.							
20	Ladder to access Mumty & Overhead tank.	Structural steel work in built up sections/framed work with handrail, proper fixing arrangement to Terrace slab and walls as/approved drawing & specifications. All structural steel to be finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint..							
21	Railing (Staircase & Other Areas)	304 Grade Stainless Steel in All Staircase, corridor areas & building entry ramps.							

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
GUEST HOUSE									
1	Dormitory Rooms 1 & 2	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	Utility/Control Room	25mm thk. Polished Kota Stone	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
3	Store	25mm thk. Polished Kota Stone	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
4	Kitchen	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	Vitrified Tile upto 2.1m height of 600 x 600 mm or appropriate size as per approved drawings.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
5	Dining Area	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specifacaton/drawing		Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
6	Toilets of dormitories including WC & Bath, H. Toilet	Rectified Anti-skid Ceramic Tile 300 x 300 mm including grouting the joints.	Dado: Ceramic Tiles of size 300 x 450 mm up to False Ceiling Level on all internal walls including partitions.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type 30 mm thk. flush Door shutter having min. density 650 Kg/cum.	Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.		15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles.
7	Corridor & Lift Lobby on all floors	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre-moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) (100 mm high) all around excluding Lift façade. 18 mm thick mirror polished granite on Lift Façade (facia & jambs) upto Ceiling Height.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	On Ground Floor 2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	On Ground Floor Double Leaf 35 mm thick Flush Door shutters decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
GUEST HOUSE									
8	Staircase on all floors	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre-moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	1.Double leaf fire door as per specifications for staircase/exit pathways/refuge areas 2.FHC shaft door as per Fire/NBC norms.		Powder Coated (minimum 50 micron coating) Aluminium partially Sliding/Fixed window with 5mm clear Glass glazing over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster. Note: 6 mm plaster has to be done on waist slab (bottom & side both) and landing slab.
9	Reception & Waiting Area	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre-moulded & pre-polished double nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) (100 mm high) all around.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specificaton/drawing		-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
10	Entrance Porch Area with steps	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre-moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of steps.	Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 18mm cement plaster in two coats.	Frameless toughened glass door & partition with privacy films as per Specificaton/drawing		-	-	Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 6 mm cement plaster.
11	Balconies of rooms (Dormitory 1 to 4, Multipurpose room, Staff room, Room-01 to 23)	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 18mm cement plaster in two coats.	uPVC sliding doors with wire mesh panel as per specification & drawings				Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 6 mm cement plaster.
12	Multipurpose Room, Staff Room	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.			Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
13	Dormitory Rooms 3 & 4	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.			Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
14	Rooms-01 to 23	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.			Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
GUEST HOUSE									
15	Toilets of Staff room & Rooms - 01 to 23	Rectified Anti-skid Ceramic Tile 300 x 300 mm including grouting the joints.	Dado: Ceramic Tiles of size 300 x 450 mm up to False Ceiling Level on all internal walls including partitions.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type 30 mm thk. flush Door shutter having min. density 650 Kg/cum.	Mechanical Ventilation in all rooms except in Staff room, Room-03, 08, 13, 18 & 23 In Staff room, Room-03, 08, 13, 18 & 23 - Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.		15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles.
16	Common area on first, second & third floor	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre-moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) (100 mm high) all around.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.			-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
17	Balcony of common areas on first, second & third floor	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 18mm cement plaster in two coats.	Frameless toughened glass door & partition with privacy films as per Specification/drawing				Premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer over water proof cement based putty above 6 mm cement plaster.
18	House Keeping Rooms	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
19	Mumty	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre-moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Internal walls painted with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	1. Double leaf fire door as per specifications for staircase/exit pathways/refuge areas etc. 2. FHC shaft door as per Fire norms.		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
20	All External walls including Parapet (including top & terrace slab side of parapet), terrace slab side of Lift overhead, shafts, mumty, overhead tanks at Terrace etc.	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
21	Shafts (Lift, Services - Electrical, Fire, LV, Plumbing)	Waterproofing in Lift pit as per specifications		White washing with lime over 12mm cement plaster.	Doors of Electrical shaft to be as per NBC and CPWD specifications with latest amendment. Door for LV shaft is MS frame & shutter with ventilator arrangement as/drawing. Door of FHC shaft as per applicable guidelines NBC/CPWD.		For Plumbing shafts - Powder Coated (minimum 50 micron coating) Aluminium frame & Shutter with Louvers		-
22	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							
23	Balcony Railing	230 high Concrete wall/beam with 970mm high Stainless Steel railing of grade 304. 18mm thick gang saw cut granite of approved colour & shade, edges rounded and projecting 12mm from finished wall surface at balcony sill.							

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
GUEST HOUSE									
24	Accessible & Non-accessible terrace (like terrace slab of towers, mumty, lift overhead, Overhead water tank, shafts (if required)	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							
25	Kitchen Counter platform, shelves, partitions, drop, facias	Commercial Kitchen setup as per specifications including supply, installation, commissioning of equipments as per approved drawings & direction of Engineer-in-charge							
26	Railing (Staircase & Other Areas)	304 Grade Stainless Steel in All Staircase, entry steps & building entry ramps.							
27	Entry Ramp	18 mm Thk. Polished Granite with 100mm anti-skid strips - (Black,Cherry/ruby Red or equivalent) & Stainless steel grade 304 railing							
28	Ladder to access Mumty & Overhead tank.	Structural steel work in built up sections/framed work with handrail, proper fixing arrangement to Terrace slab and walls as/approved drawing & specifications. All structural steel to be finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint..							

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
Community Centre									
1	Utility Rooms on all floors	25mm thk. Polished Kota Stone of appropriate size	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles as per relevant drawing and specification.
2	ATM	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS rolling shutter (with mechanical device for opening) finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		-	-	15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles as per relevant drawing and specification.
3	Front Entrance Verandah, Corridor/steps	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/ Landings/floor Granite shall be pre- moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of steps.	Internal walls of corridor finished with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films at front entry to building corridor & common hall as per Specificaton/drawing		-	-	For corridor - Gypsum board false ceiling as per relevant drawing & specification finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.
4	Side Entrance/steps	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/ Landings/floor Granite shall be pre- moulded & pre-polished double nosing. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of steps.	Internal walls finished with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Double leaf fire door as per specifications/drawing for Staircase/Exit pathway		-	-	
5	Staircase on all floors	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre- moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	For fire staircase - Double leaf fire door as per specifications for staircase/exit pathways/refuge areas		Powder Coated (minimum 50 micron coating) Aluminium partially Sliding/Fixed window with 5mm clear Glass glazing over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster. Note: 6 mm plaster has to be done on waist slab (bottom & side) and landing slab.
6	Common hall	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Door from Front Entry Corridor 2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	Door from Front Entry Corridor 35 mm thick double leaf Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Calcium silicate & Gypsum board False ceiling as per relevant drawing & specifications. Gypsum board false ceiling shall be finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
Community Centre									
7	Office & Office/Record	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof/SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.	Calcium silicate & Gypsum board False ceiling as per relevant drawing & specifications. Gypsum board false ceiling shall be finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.	
8	Toilets (Male, Female, Divyang) on all floors	Anti-skid Ceramic Tile 300 x 300 mm including grouting the joints.	Dado: Ceramic Tiles of size 300 x 450 mm up to False Ceiling Level on all internal walls including partitions.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 30 mm thk. flush Door shutter having min. density 650 Kg/cum.	Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.	15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles as per relevant drawing & specifications.	
9	D. Water area on all floors	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	Vitrified Tile upto False ceiling height of 600 x 600 mm or appropriate size as per approved drawings.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	-	-	-	-	Gypsum board false ceiling as per relevant drawing & specification finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.
10	Meeting room	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specification/drawing		Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof/SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint	15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles as per relevant drawing & specifications.	
11	Indoor Gym/activity area	25mm thk. Wooden flooring with 2nd class teak wood	100mm high Wooden 2nd class teak wood (12 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specification/drawing		Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof/SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint	Calcium silicate & Gypsum board False ceiling as per relevant drawing & specifications. Gypsum board false ceiling shall be finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.	
12	Passage	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	-	-	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof/SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint	Gypsum board false ceiling as per relevant drawing & specification finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.	

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
Community Centre									
13	Kids sports room	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specificaton/drawing		Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Calcium ciliate & Gypsum board False ceiling as per relevant drawing & specifications. Gypsum board false ceiling shall be finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.
14	Indoor sports room	Matt/Antiskid finish Glazed Vitrified Tiles of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Frameless toughened glass door & partition with privacy films as per Specificaton/drawing		Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Calcium ciliate & Gypsum board False ceiling as per relevant drawing & specifications. Gypsum board false ceiling shall be finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.
15	Corridor on outside of Office/Record	18 mm Thk. Polished Granite- (Black,Cherry/ruby Red or equivalent) Note: All free Edges for Treads/Landings/floor Granite shall be pre- moulded & pre-polished double nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Internal walls of corridor finished with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	2nd class teak wood frame (minimum size 100X60 mm for single shutter) with 2nd class teak wood beading of size 50x12 mm. Wood work finished with wood primer and synthetic enamel paint.	35 mm thick double leaf Flush Door shutter decorative type with 1 mm thick Laminate on both sides and 2nd class teak wood lipping finished with wood primer & synthetic enamel paint on all edges.	Three track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Gypsum board false ceiling as per drawing finished with Cement Based Putty and Internal Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.
16	Store	25mm thk. Polished Kota Stone of appropriate size	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster above dado.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 30 mm thk. flush Door shutter having min. density 650 Kg/cum.	Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.		15 mm thick densified tegular edged ecofriendly light weight calcium silicate false ceiling tiles as per relevant drawing & specifications.
17	Mumty	18 mm Thk. Polished Granite- (Black, Cherry/ruby Red or equivalent) Note: All free Edges for Treads & Landings Granite shall be pre-moulded & pre-polished double nosing in staircase. All treads/steps to have anti-skid grooves near nosing.	18 mm thick polished Granite skirting (Black,Cherry/ruby Red or equivalent) in skirting (100mm high) and riser of staircase.	Internal walls painted with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	For normal staircase - MS shutter with MS frame finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint. Double leaf fire door as per specifications/drawing for Fire escape staircase.		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint only in Fire staircase window.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
18	All External walls including Parapet (including top & terrace slab side of parapet), terrace slab side of shafts, mumty, overhead tanks at Terrace etc.	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
19	Shafts	-	-	White washing with lime over 12mm cement plaster.	Door of FHC shaft as per applicable guidelines NBC/CPWD. Door for LV shaft is MS frame & shutter with ventilator arrangement as/drawing.		For Plumbing shafts - Powder Coated (minimum 50 micron coating) Aluminium frame & Shutter with Louvers		-
20	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
Community Centre									
21	Entry porch/steps Railing	Stainless Steel railing of grade 304.							
22	Accessible & Non-accessible terrace (like terrace slab, mummy, Overhead water tank, shafts (if required)	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							
23	Entry Ramp	18 mm Thk. Polished Granite with 100mm anti-skid strips - (Black,Cherry/ruby Red or equivalent) & Stainless steel grade 304 railing							
24	Ladder to access Mummy & Overhead tank.	Structural steel work in built up sections/framed work with handrail, proper fixing arrangement to Terrace slab and walls as/approved drawing & specifications. All structural steel to be finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.							

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
Sub-station & Panel Room / Electrical Sub-station									
1	HT panel room	25mm thk. Kota Stone of appropriate size	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS door with MS frame finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint; MS rolling shutter (with mechanical device for opening) finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	LT panel room	25mm thk. Kota Stone of appropriate size	100mm high Kota Stone (20 mm thick) skirting all around	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS rolling shutter (with mechanical device for opening) finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
3	Transformer room	62mm thick CC flooring 1:2:4 with concrete hardener topping	100mm high Kota Stone (20 mm thick) skirting	Internal walls finished with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS rolling shutter (with mechanical device for opening) finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Two track Aluminium Sliding Window of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
4	All External walls including Parapet (including top & terrace slab side of parapet)	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
5	Entery steps, open porch	25mm thick kota stone flooring with 20mm thick kota stone riser							
6	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							
7	Accessible & Non-accessible terrace	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							
8	External Entry Ramp	RCC flooring with broom finish							
9	Around DG sets	Chainlink fencing with Gate and flooring with 150mm thick 1:2:4 Cement concrete with floating coat of neat cement, 150mm Sand filling beneath around DG set as per approved drawing, specification & direction of Engineer-in-charge.							
Guard room with CCTV									
1	Guard room	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 25 mm thk. flush Door shutter having min. density 650 Kg/cum.	Three track Aluminium Sliding/Partially fixed Window (as/approved drawing) of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	CCTV room	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 25 mm thk. flush Door shutter having min. density 650 Kg/cum.	Three track Aluminium Sliding Window (as/approved drawing) of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
3	Toilet	Anti-skid Ceramic Tile 300 x 300 mm including grouting the joints.	Dado: Ceramic Tiles of size 300 x 450 mm up to False Ceiling Level on all internal walls.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 25 mm thk. flush Door shutter having min. density 650 Kg/cum.	Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 4mm thk. frosted Glass and Exhaust Fan. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.		Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
4	All External walls including Parapet (including top & terrace slab side of parapet)	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
5	Entery steps, open porch	25mm thick kota stone flooring with 20mm thick kota stone riser							
6	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							
7	Accessible & Non-accessible terrace	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							

Security Hut								
1	Room	Polished Glazed Vitrified Tile of size 800 x 800 mm finished with matching grout.	100 mm high Vitrified Tile all around matching the floor material & size.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	Factory made WPC (Wood polymer composite) solid Door Frame of size 50 x 100mm having minimum frame density of 750 Kg/cum.	Factory made single extruded WPC (Wood polymer composite) solid decorative type min. 25 mm thk. flush Door shutter having min. density 650 Kg/cum.	Three track Aluminium Sliding Window (as/approved drawing) of Powder Coated (minimum 50 micron coating) with 5mm Float Glass glazed shutters integrated with mosquito/flyproof SS 304 mesh shutter over 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at window sill. MS grill also to be provided on outer side finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	All External walls including Parapet (including top & terrace slab side of parapet)	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.						
3	Entry steps, open porch	25mm thick kota stone flooring with 20mm thick kota stone riser						
4	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.						
5	Accessible & Non-accessible terrace	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.						

Pump room & UGWT								
1	Pump room	Water proofing treatment as/specification. With 25mm thk. Kota Stone of appropriate size on floor.	Haunching/fillet at wall & floor slab edges as per approved drawings & specifications	Waterproofing with 12mm cement plaster surface as per specifications finishing with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture.	-	-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
2	Entry Porch/room, steps, Fire & Plumbing panel room	25mm thk. Kota Stone of appropriate size on floor & single slab on treads of steps	Kota Stone (20 mm thick) in skirting (100mm) and in risers.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 12 mm cement plaster.	MS door with MS frame finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint; MS rolling shutter (with mechanical device for opening) finished with ready mixed red oxide zinc chromate primer & synthetic enamel paint		Powder Coated (minimum 50 micron coating) fixed Aluminium Frame with 5mm thk. Float Glass as/approved drawing. 18 mm thick gang saw cut black granite, edges rounded and projecting 12mm from finished wall surface at sill.	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster.
3	Staircase	Single slab 25mm thk. Kota Stone on treads	Kota Stone (20 mm thick) in skirting (100mm) and in risers.	MS Railing finished with ready mix red oxide zinc chromate primer & synthetic enamel paint	-	-	-	Painting with acrylic emulsion paint of approved shade with primer of interior grade. The paint & primer shall have VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture over Cement Based Putty above 6mm cement plaster. Note: 6 mm plaster has to be done on waist slab (bottom & side) and landing slab.
4	Water tank	Water proofing as per specifications finishing with ceramic tiles	Water proofing as per specifications finishing with ceramic tiles till full height	Waterproofing with 12mm cement plaster surface as per specifications				6mm cement plaster

SCHEDULE OF FINISHES - CIVIL - To be read in conjunction with relevant drawings/specifications/other relevant information of Tender Document									
SN	LOCATION	FLOOR	SKIRTING/DADO	WALL	DOOR		WINDOW/VENTILATOR		CEILING
					Frame	Shutter	Frame	Shutter	
5	All External walls including Parapet (including top & terrace slab side of parapet)	18mm Plaster in two coats, providing grooves on beam, column junction with masonry finished with – Textured Exterior Paint of Approved Shade over waterproof cement based putty.							
6	Entery steps, open porch	25mm thick kota stone flooring with 20mm thick kota stone riser							
7	Projection/Chajja	Top to be Graded with cement mortar 1:3 as per CPWD specifications, providing haunching/fillet at edges with wall & painting.							
8	Accessible & Non-accessible terrace	Self healing liquid rubber water proofing, laying CC 1:2:4 concrete for roof grading, providing haunching/fillet at wall & slab edges, providing heat resistant SRI tiles as per specifications.							
OTHER AREAS									
1	Footpath/Ramps	60 mm thick precast cement concrete paver block (M-30) & tactile flooring as per approved drawings & specifications.							
2	Internal/External Road & On-street Parking	Cement Concrete Road as per approved drawing & specifications.							
3	Kerb Stone	M-25 Precast cement concrete kerb stones as per specifications and approved design.							
4	Parking Shed	Cantilever Structural steel duly finished with ready mix red oxide zinc chromate primer & synthetic enamel paint with pre-coated corrugated/profiled Galvanized roofing Sheet (GS) as per approved drawings & specifications							
5	Boundary Wall	As per drawings (Eccentric/Concentric footing with earth retaining as per site conditions, weep holes) & specifications with RCC frame with brick work concertina coil fencing and finished with 12mm cement plaster and premium acrylic emulsion paint (Company depot tinted) of approved shade having VOC less than 50 gm/litre and UV resistance, alkali & fungal resistance, dirt resistance exterior paint with silicon additives including primer.							

SANITARY & PLUMBING WORKS

(To be read in conjunction with relevant drawings/specifications/other relevant information of tender document)

A. Sanitary Fittings

SN	Description	Location
Residential Towers		
1.	Fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litre with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc. including making connection with the P/S trap, complete in all respect including: • Health faucet • CP brass 2-way bib cock	1 No. in each Toilet
2.	Flat back wash basin (550X400mm)	1 No. in each Toilet and Living/Dining Room
3.	CP Brass mixture type for hot & cold water with single lever quarter turns faucet for wash basin	1 No. for each wash basin
4.	CP brass Bath & Shower Mixer 3-in-1 System with Provision for hand shower & Overhead Shower Complete with 115mm Long Bend Pipe, Wall Mounted	1 No. in each Toilet at shower area
5.	C.P. brass shower rose with 15 or 20 mm inlet and 150 mm dia with shower tail length of 450 mm for over head shower	1 No. in each Toilet at shower area
6.	CP Brass 32 mm size Bottle Trap	1 No. for each Wash basin
7.	C.P. brass angle valve	02 No. for each Wash basin, 02 Nos. each for geyser in toilets & kitchen, 01 No. for each Water closet, 02 Nos. for each kitchen sink, 01 No. for each RO in Kitchen
8.	PVC connection pipe with brass unions	02 No. for each Wash basin, 02 Nos. each for geyser in toilets & kitchen, 01 No. for each Water closet, 02 Nos. for each kitchen sink,
9.	Plumbing for Geyser	In each Toilet & Kitchen

SN	Description	Location
10.	Towel rail & Towel Ring of SS grade 316	1 No. towel rail in each Toilet 1 no. towel ring for each Wash basin.
11.	Mirror of superior glass with plastic moulded frame and 6mm thick hard wood backing supported on CP brass screws. (Size 450X600mm) with Glass shelf	1 No. with each wash basin
12.	Toilet paper holder of SS grade 316 with European WC	1 No. in each Toilet
13.	Soap dish holder	2 Nos. in each Toilet
14.	Liquid Soap container	1 No. with each Wash Basin
15.	Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless-steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required • Kitchen sink with drain board size 510X1040 mm bowl depth 200 mm • SS Waste Coupling, • P.V.C. waste pipe • Swan faucet Tap, Silver, Chrome finish for hot & cold mixture	1 No. in each Kitchen
16.	Plumbing for water purifier	In each Kitchen
17.	Long body Bib Cock for Washing Machine	In each Utility Balcony
18.	Grab Bars	In common toilet to be provided for especially abled/elderly members in 16 flats of first floor.
19.	Ball Valve	1 no. each for domestic & flushing water supply lines after entry to each toilet & Kitchen of every flat.
Guest House		
1.	White vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete. • Health faucet • CP brass 2way bib cock	1 No. in each Toilet of Rooms & 02 Nos. each in Toilets of Dormitories

SN	Description	Location
2.	Under Counter wash basin with 18 mm thick mirror polished edge moulded granite	1 No. in each Toilet of Rooms, 02 Nos. each in Toilets of Dormitories & 02 Nos. in Dining Area
3.	CP Brass mixture type for hot & cold water with single lever quarter turns faucet for wash basin	1 No. for each wash basin
4.	Bath & Shower Mixer 3-in-1 System with Provision for Hand Shower & Overhead Shower Complete with 115mm Long Bend Pipe, Wall Mounted	1 No. in each Toilet of Rooms & 02 Nos. each in Toilets of Dormitories
5.	C.P. brass shower rose with 15 or 20 mm inlet and 150 mm dia with shower tail length of 450 mm for over head shower	1 No. in each Toilet of Rooms & 02 Nos. each in Toilets of Dormitories
6.	CP Brass 32 mm size Bottle Trap	1 No. for each Wash basin
7.	C.P. brass angle valve	02 No. for each Wash basin, 02 Nos. each for geyser in every bath area of rooms, dormitories, 01 No. for each Water closet 12 Nos. for kitchen washing area 01 No. for RO
8.	PVC connection pipe with brass unions	02 No. for each Wash basin, 02 Nos. each for geyser in every bath area of rooms, dormitories, 01 No. for Water closet, 12 Nos. for kitchen washing area,
9.	Plumbing for Geyser	In each Toilet & Kitchen
10.	Towel rail & Towel Ring of SS grade 316	1 No. towel rail in each shower area of rooms and dormitories toilet 1 no. towel ring for each Wash basin.
11.	Mirror of superior glass with plastic moulded frame and 6mm thick hard wood backing supported on CP brass screws. (size 450X600mm) with glass shelf	1 No. with each wash basin
12.	Toilet paper holder of SS grade 316 with European WC	1 No. for each WC
13.	Soap dish holder	2 Nos. in each Shower Areas of room & dormitories toilet
14.	Liquid Soap container	1 Nos. with each Wash Basin
15.	Stainless Steel kitchen sink	As per Kitchen specification In Technical

SN	Description	Location
	•SS Waste Coupling, •P.V.C. waste pipe •Swan faucet Tap, Silver, Chrome finish with hot & cold-water mixer	Specification and as mentioned in drawings
16.	Plumbing for water purifier	1 No. in kitchen
17.	White vitreous China battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre & post flushing with water (250 ml & 500 ml consumption)	01 No. in each Dormitory with Granite urinal partitions
18.	Handicap toilet	01 No. each of WC, Sensor Urinal, Wash Basin, Toilet paper Holder, Soap Dispenser, Hand Dryer, Mirror, Health Faucet, Angle Valve, CP Brass mixture type for hot & cold water with single lever quarter turns faucet, PVC connection pipe with brass unions, grab bars for of Handicap Toilet with full relevant sanitary fittings as per IS /CPWD specifications
19.	Ball Valve	1 no. each for domestic & flushing water supply lines after entry to each toilet & Kitchen
Community Centre		
1.	White vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete. •Health faucet •CP brass 2way bib cock	10 Nos. (04 Nos. in Male Toilet & 06 Nos. in Female Toilet)
2.	Under Counter wash basin with 18 mm thick mirror polished edge moulded granite	8 Nos. (04 Nos. in Male Toilet & 04 Nos. in Female Toilet)
3.	CP Brass mixture type for hot & cold water with single lever quarter turns faucet for wash basin	1 No. for each wash basin
4.	CP Brass 32 mm size Bottle Trap	1 No. for each Wash basin
5.	C.P. brass angle valve	2 No. for each Wash basin,

SN	Description	Location
		01 for each Water closet & 01 No. for each RO
6.	PVC connection pipe with brass unions	02 No. for each Wash basin, 01 No. for each Water closet,
7.	Tower rail of SS grade 316	1 No. in each Toilet
8.	Plumbing for RO	At Each floor
9.	Mirror of superior glass with plastic moulded frame and 6mm thick hard wood backing supported on CP brass screws. (size 450X600mm)	1 No. with each wash basin
10.	Toilet paper holder of SS grade 316 with European WC	1 No. for each WC
11.	Liquid Soap container	2 Nos. in each Toilet
12.	Solid state, no touch operating, fully hygienic hand drier	01 No. in each Toilet
13.	China battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre & post flushing with water (250 ml & 500 ml consumption),	05 Nos. in each Male Toilet with granite partitions
14.	Handicap toilet	01 No. each of WC, Sensor Urinal, Wash Basin, Toilet paper Holder, Soap Dispenser, Hand Dryer, Mirror, Health Faucet, Angle Valve, CP Brass mixture type for hot & cold water with single lever quarter turns faucet, PVC connection pipe with brass unions, grab bars for of Handicap Toilet with full relevant sanitary fittings as per IS /CPWD specifications
15.	Ball Valve	1 no. each for domestic & flushing water supply lines after entry to each toilet
16.	Polyethylene water storage tank	2 Nos. at terrace of required capacity
Guard Rooms		
1.	White vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete. • Health faucet	1 in each Toilet

SN	Description	Location
	• CP brass 2way bib cock	
2.	Flat back wash basin (550X400mm)	1 No. in each Toilet
3.	CP Brass mixture type for hot & cold water with single lever quarter turns faucet for wash basin	1 No. for each wash basin
4.	CP Brass 32 mm size Bottle Trap	1 No. for each Wash basin
5.	C.P. brass angle valve	2 No. for each Wash basin & 01 for each WC
6.	Plumbing for Geyser in Toilet	1 No. in each Toilet
7.	Tower rail of SS grade 316	1 No. in each Toilet
8.	Mirror of superior glass with plastic moulded frame and 6mm thick hard wood backing supported on CP brass screws. (Minimum size 450X600mm)	1 No. with each wash basin
9.	Toilet paper holder of SS grade 316 with European WC	1 No. in each Toilet
10.	Liquid Soap container	1 No. in each Toilet
11.	China battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre & post flushing with water (250 ml & 500 ml consumption)	01 No. in each Toilet
12.	Ball Valve	1 No. each for Water Supply & Flushing Lines in each toilet
13.	Polyethylene water storage tank	2 Nos. at each terrace of required capacity

Note: All CP & Sanitary Fittings and fixtures will be of best quality as approved by Engineer In charge and exclusively be of one manufacturer.

B. Plumbing/Sewerage/Drainage/STP work brief - (Internal & External)

1. Water Supply System		
SN	Description	Location
1.	Pipe	CPVC pipe for water supply from underground water tank to OH tank
2.	External Pipeline	CPVC Pipes as per specification
3.	Piping-Exposed on Terrace	CPVC Pipes as per specification
4.	Internal Piping-Exposed on wall	CPVC Pipes as per specification
5.	Internal Piping Concealed work	CPVC Pipes as per specification
6.	Piping in Pump Room	GI Pipes as per specification
7.	Piping for AC drainage	AC drain PVC pipes till nearest drain point
8.	Sluice Valve	sluice valve (with cap) complete with bolts & nuts, rubber insertion etc. at ground floor level of all buildings
9.	Gate Valve, Ball Valve, Float Valve, Butterfly Valve	As per drawings & requirements as approved by Engineer-in-charge.
10.	Chambers for Stop cock, Sluice Valve, water meter, garden hydrant, valve chamber	As per specification/drawings as approved by Engineer-in-charge.
11.	C.I. dirt box strainer	C.I. dirt box strainer for water meter with nuts bolts, rubber insertions etc.
12.	Pressure gauges	Industrial type pressure gauges with gun metal/ brass valves complete at Pump Room & Terrace Floor.
13.	C.I. double acting air valve	C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete at water supply pipe in riser
14.	Water Supply Pump	Domestic and Flushing water pump water filling from UGT to Over Head Tank in pump room
15.	OH Tank	RCC OH tank of required capacity with covers, footrests and necessary installation all complete for supply of water as per drawings, design and scheme as approved by the Engineer- in charge. This shall consist of provisions for drinking water chambers, firefighting chamber and flushing system. Syntex water tank as per drawings/specifications.
16.	UGT/Pump House	RCC tank of required capacity with covers, footrests and necessary installation all complete for supply of water including standby Pump as per drawings, design and scheme as approved by the Engineer- in charge. This shall consist of provisions for drinking water chambers, firefighting chambers, flushing & horticulture system etc.

2. Sewerage System

SN	Description	Location
1.	Pipe and fittings	uPVC pipes (soil, waste & vent pipes) with solvent cement joint for 8 kg/ sq. cm. pressures including testing of joints, jointing materials all fitting, accessories etc. complete in all respect.
2.	DWC pipes	Double wall corrugated HDPE pipes SN 8 for sewerage application with socket and EPDM rubber ring joints, all fittings, including testing of joints etc. complete conforming to IS:16058 part-2 as per specifications and drawings as approved by Engineer-in-charge.
3.	Manhole for sewer Line	a) Brick masonry circular manhole 0.91 m internal dia at bottom and 0.56 m dia at top with 901 to 1650 mm deep with SFRC Cover and frame at main Line. b) Brick masonry circular manhole 1.22 m internal dia at bottom and 0.56 m dia at top with 1651 to 2300 mm deep with SFRC Cover and frame at main Line. c) Brick masonry rectangular manhole 800X900 mm and 0.60 to 0.90m deep with SFRC Cover around the Buildings outlets. As per specifications and drawings as approved by Engineer-in-charge.
4.	Foot Rest	Orange colour safety foot rest of minimum 6mm thick plastic encapsulated complete as per IS: 10910 as per drawings & specifications.
5.	Drop connection	For drop more than 0.610m drop connection as per CPWD Specifications to be provided.
6.	Gully Trap	Brick masonry Gully trap 30X30 cm inside with bricks in cement mortar 1:4 as per specifications and drawings as approved by Engineer-in-charge.

3. Drainage System		
SN	Description	Location
1.	Rain Water Pipes	Un-plasticized - PVC rain water pipes as per specifications
2.	Manholes	a) Brick masonry circular manhole 0.91 m internal dia at bottom and 0.56 m dia at top with 901 to 1651 mm deep with SFRC Cover and frame at main Line. b) Brick masonry circular manhole 1.22 m internal dia at bottom and 0.56 m dia at top with 1651 to 2300 mm deep with SFRC Cover and frame at main Line. c) Brick masonry rectangular manhole 800X900 mm and 0.60 to 0.90m deep with SFRC Cover around the Buildings outlets As per specifications and drawings as approved by Engineer-in-charge.
3.	Footrest	Orange colour safety foot rest of minimum 6mm thick plastic encapsulated complete as per IS: 10910 as per drawings & specifications.
4.	NP2 class (Heavy duty)	Non-pressure NP2 class (heavy duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. for connection to RCC covered drain channel starting from catch basin.
5.	Catch basin	Catch basin 450x450 mm (depth variable as per site) with CI cover frame complete as per drawings and specifications as approved by Engineer-in-charge.
6.	Storm Water Drain	Covered RCC Storm Water Drain size as per design. At road crossing box drain to be provided.
7.	Rainwater Harvesting Pit	Six rainwater harvesting pits with all necessary boring, pipes, connections, spreading & levelling stone boulders, spreading & levelling gravels, sand etc. with Modular Recharge pit and De-Silting Chamber, Grease trap as per specifications and drawings as approved by Engineer-in-charge.
8.	Rainwater pipe and Fittings	Un-plasticized PVC (Type A) pipe and Un-plasticized PVC moulded fittings & accessories at stilt and riser line.
9.	Plastering	12mm cement plaster in CM 1:3 (1 cement: 3 coarse sand) with neat finish inside and top of raft of drain.
10.	Covers	Minimum M-25 RCC perforated & non perforated Covers shall be provided to cover all the drains.
11.	Saucer Drain with gully traps & gratings	Precast saucer drains as per site requirement

4. STP -Moving Bed Biological Reactor (MBBR) with Ultra-filtration unit		
SN	Description	Location
1.	STP -Moving Bed Biological Reactor (MBBR) with Tertiary treatment integrated with Ultra-filtration unit & Treated water underground tank for Irrigation & Flushing Tank	Design, Supply Install & Commissioning of STP with Treated water tanks (Irrigation & Flushing) as per DBR including Civil, Electrical, Mechanical, Instrumentation, Piping, Fittings and Valves, Electrical Panel, Wiring & Cabling and Miscellaneous all complete as per relevant IS codes & Direction of Engineer-in-charge. Treated water tank of STP should have sensor to monitor the treatment performance within the desired parameters.

Note: In case any information is not specifically mentioned in Schedule of Finishes then same to be referred from drawings, technical specifications, scope of work etc. of tender document as per decision & directions of Engineer-in-charge.